# EXHIBIT C TRILOGY HEALTH SERVICES, LLC

PATIO HOMES AT PRAIRIE LAKES NOBLESVILLE PRELIMINARY DEVELOPMENT PLAN PRAIRIE LAKES BLVD. E

CITY OF NOBLESVILLE, COUNTY OF HAMILTON, STATE OF INDIANA

# **BENCHMARKS**

X-NOTCH ON NE RIM OF SANITARY MANHOLE, 92 FEET WEST OF SW CORNER OF EXISTING BUILDING AND 6


X-NOTCH ON WESTERLY BACK OF CURB OF PRAIRIE LAKES BLVD. N, 6 FEET SOUTH OF MOST SOUTHERLY

X-NOTCH ON NW RIM OF SANITARY MANHOLE, 134 FEET NORTH OF CENTERLINE OF PRAIRIE LAKES BLVD. N AND 99 FEET NORTH OF EXISTING FIRE HYDRANT.

§ INCH IRON PIN. LOCATED ON THE NORTH EAST MOST CORNER. APPROXIMATELY 82 FEET NORTH OF EASTING: 235271.72







# INDEX OF SHEETS

TITLE SHEET	1
EXISTING CONDITIONS AND DEMOLITION	
OVERALL SITE PLAN	
OVERALL UTILITY PLAN	
OVERALL GRADING PLAN	
STREET TREE PLAN	
LANDSCAPE PLAN	
LANDSCAPE NOTES AND DETAILS	
PHOTOMETRIC PLAN	

NOT FOR CONSTRUCTION

# **UTILITY CONTACTS**

SANITARY SEWERS
HAMILTON SOUTHEASTERN UTILITIES, INC. 11901 LAKESIDE DR. FISHERS, INDIANA 46038 PHONE: 317-557-2300

INDIANA AMERICAN WATER-NOBLESVILLE 15227 HERRIMAN BLVD. NOBLESVILLE, IN 46060 CONTACT: JOSHUA COX PHONE: 317-900-4975 EMAIL: JOSHUA.COX@AMWATER.COM

CONTACT: RANDY CRUTCHFIELD

PHONE: 317-776-5336 FMAIL: FRIC.LONG@DUKF-FNFRGY.COM

CONTACT: WENDY NOBLE PHONE: 317-610-5436 EMAIL: WENDY.NOBLE@ATT.COM

# PROJECT CONTACTS

<u>DEVELOPER</u> TRILOGY HEALTH SERVICES, LLC. 305 N. HURSTBOURNE PARKWAY, SUITE 200 PHONE: (502) 396-0493

EMAIL: EARL.CRAMER@TRILOGYHS.COM UNIVERSAL DESIGN ASSOCIATES, INC. 910 MAIN STREET/P.O. BOX 99 FERDINAND, IN 47532 ATTN: JON SCHNARR PHONE: 812-367-2831 JONSCHNARR@UDASSOC.COM

# CLOSEOUT

THE GENERAL CONTRACTOR SHALL COORDINATE THE CLOSEOUT OF THE PROJECT. THE CLOSEOUT SHALL BE AS REQUIRED TO ENSURE A SMOOTH AND COMPLETE PROCESS, AND NOT INTERFERE WITH TRILOGY'S TAKE OVER OF THE STATE FIRE MARSHALL, STATE HEALTH DEPARTMENT, LIFE SAFETY, LOCAL APPLICABLE AGENCIES, AND THE VIP OPENINGS. GENERAL CONTRACTOR IS RESPONSIBLE FOR SCHEDULING STATE AND LOCAL AGENCIES FOR REQUIRED INSPECTIONS.

THE GENERAL CONTRACTOR IS RESPONSIBLE FOR COORDINATING THE SUPPLIERS' DELIVERY OF MATERIALS AND WORK. ITEMS INCLUDED ARE: FIRE ALARM, NURSE CALL, KITCHEN EQUIPMENT, KITCHEN HOOD, FIRE SUPPRESSION SYSTEM FOR THE HOOD, DISHWASHER HOOD, WONDERGUARD SYSTEM, MAGLOCK SYSTEM, PHONE, AND DATA SYSTEM, ETC.

ALL FINISH FLOORING SHALL BE INSTALLED AS NEAR TO THE END OF CONSTRUCTION AS POSSIBLE. ALL FLOORING THAT IS INSTALLED PRIOR TO COMPLETION OF CONSTRUCTION SHALL BE PROTECTED BY TEMPORARY COVERING. IN THE EVENT THE FINISH FLOORING IS SOILED OR DAMAGED, IT SHALL BE COMMERCIALLY CLEANED OR REPLACED. ONLY VACUUMING WILL NOT BE

THE HVAC TEST AND BALANCE MUST BE PERFORMED, ADJUSTED AS NECESSARY, APPROVED AND CERTIFICATES PROVIDED AND ALL ATTIC INSULATION MUST BE IN PLACE PRIOR TO THE FINAL COMPLETION BEFORE ANY FURNITURE OR ACCESSORIES ARRIVE TO THE BUILDING.

GENERAL CONTRACTOR AND SUB-CONTRACTORS MUST DO THEIR OWN COMPLETE INSPECTIONS (PUNCH LIST) AND CORRECT ALL ITEMS PRIOR TO HAVING ENGINEER DO THEIR INSPECTION AND PUNCH LIST.


THE ENTIRE PROJECT CONSTRUCTION SHALL BE ONE HUNDRED PERCENT (100%) COMPLETE PRIOR TO ENGINEER/OWNER FINAL INSPECTION (PUNCH LIST) BEING PERFORMED. AFTER THE PUNCH LIST IS PROVIDED, ALL ITEMS MUST BE CORRECTED IMMEDIATELY FOR REINSPECTION TO VERIFY COMPLETION. THE ENTIRE PUNCH LIST MUST BE COMPLETE PRIOR TO OBTAINING THE CERTIFICATE OF OCCUPANCY.

THE TRILOGY TEAM WILL NOT PROVIDE RESOURCES AND MANPOWER TO GET THE BUILDING READY FOR THE CLOSEOUT PROCEDURES AND FURNITURE/ACCESSORIES INSTALLATION. THE BUILDING MUST BE COMPLETE INCLUDING THE PUNCH LISTS PRIOR TO THE SCHEDULED MOVE-IN OF FURNITURE AND ACCESSORIES.

FURNITURE AND ACCESSORIES ARE SCHEDULED FOUR (4) MONTHS IN ADVANCE TO BE DELIVERED AND THEREFORE CONSTRUCTION MUST STAY ON THE TIMELINE WITH NO EXCEPTION. MISSING THE CONSTRUCTION COMPLETION DATE IS SUBJECT TO A PENALTY.

IN THE EVENT THE COMPLETION OF THIS PROJECT CONSTRUCTION IS NOT ACCOMPLISHED WITHIN THE SCHEDULE, AND IF THE TRILOGY TEAM HAS TO ASSIST THE CONTRACTOR ON NON-COMPLETED WORK, TRILOGY HAS THE RIGHT TO CHARGE THE CONTRACTOR FOR ALL EXPENSES INCURRED.

THE CONTRACTOR SHALL SUBMIT THE ITEMS (CERTIFICATIONS) FOR LICENSE AND OCCUPANCY. MAINTENANCE AND WARRANTY MANUALS. AND THE AS-BUILT DRAWINGS PRIOR TO THE FINAL








TIO HOMES AT PRAIRIE LAKES NOBLESVILLE

PROJECT DATE: AUG 2024 T1730034


PROJECT NO .: DRAWN BY: CHECKED BY:







# <u>DEMOLITION LEGEND</u>



WETLAND REMOVAL



TREE REMOVAL

PAVEMENT REMOVAL



DEMOLITION CODED NOTE

# GENERAL NOTES:

- 1. CONTRACTOR TO SUPPORT AND PROTECT EXISTING UTILITIES THROUGHOUT DURATION OF CONTRACT. ALL UTILITIES ARE TO REMAIN ACTIVE.
- 2. CONTRACTOR SHALL USE CAUTION WORKING NEAR EXISTING UNDER GROUND UTILITIES.
- 3. PAVEMENT SAWCUTS SHALL BE MADE TO LEAVE A CLEAN NEAT EDGE TO UP AGAINST LOOSE OR BROKEN SEGMENTS OF PAVEMENT, AND FIX ACCORDINGLY TO PROVIDE A SOLID CLEAN
- 4. CONTRACTOR IS RESPONSIBLE FOR REPLACING ANY ONSITE ITEMS DAMAGED DURING CONSTRUCTION IN THE SAME OR BETTER CONDITION THAN THEY WERE PRIOR TO CONSTRUCTION.
- THE EXISTING TOPOGRAPHY SHOWN ON THESE PLANS IS THE SURVEY OF RECORD FOR THIS PROJECT. SHOULD THE CONTRACTOR TAKE EXCEPTION TO THE EXISTING TOPOGRAPHY AS SHOWN IN THESE PLANS THEY SHALL SUBMIT A TOPOGRAPHIC SURVEY PREPARED BY A REGISTERED PRIOR TO THE INITIATION OF ANY EARTH MOVING ACTIVATES. OTHERWISE THE TOPOGRAPHY CONTAINED WITHIN THESE PLANS IS ACCEPTED BY THE CONTRACTOR AND DEEMED ACCURATE FOR ALL GRADING AND SOILS MANAGEMENT ISSUES.
- THE CONTRACTOR IS RESPONSIBLE FOR CONSTRUCTING THE LINES AND GRADES ILLUSTRATED WITHIN THIS PLAN SET. THE CONTRACTOR IS TO INCLUDE ALL SOILS IMPORT OR EXPORT NECESSARY TO ATTAIN THE LINES AND GRADES ILLUSTRATED HEREIN WITHIN THE BASE BID OF THIS PROJECT WITH NO ADDITIONAL COST FOR SOILS IMPORT OR EXPORT.
- REFER TO IDEM PERMIT NO. IWIP 2020-387-29-ALF-A FOR ISOLATED WETLAND DISTURBANCE

- CONTRACTOR SHALL USE CAUTION WHILE WORKING NEAR EXISTING UNDERGROUND UTILITIES.
- CONTRACTOR SHALL STRIP TOPSOIL WITHIN THE CLEARING LIMITS PER GEOTECHNICAL REPORT AND STOCK PILE ON SITE. THE ACTUAL DEPTH OF TOPSOIL IS TO BE VERIFIED BY AN ONSITE GEOTECHNICAL
- CONTRACTOR SHALL DELINEATE AND PROTECT AREA OF WETLANDS TO REMAIN. NO WORK SHALL OCCUR IN PORTIONS OF THE EXISTING WETLAND.
- (4) CONTRACTOR SHALL REMOVE EXISTING TREES/SHRUBS.
- CONTRACTOR SHALL REMOVE AND REPLACE EXISTING CURB AND SIDEWALK.
- 6 CONTRACTOR SHALL ADJUST EXISTING RIM TO BE FLUSH WITH PROPOSED GRADES. SEE UTILITY PLAN.
- (7) EX LIGHT POLE TO BE RELOCATED




E S

ATIO HOMES AT PRAIRIE LAKES NOBLESVILLE

PROJECT DATE: AUG 2024 PROJECT NO.: DRAWN BY:

CHECKED BY:

EXISTING
CONDITION AND
DEMOLITION
PLAN





# PROPOSED SITE LAYOUT LEGEND

LIGHT DUTY ASPHALT PAVEMENT

PER DETAIL

HEAVY DUTY ASPHALT PAVEMENT PER DETAIL

STANDARD DUTY CONCRETE PAVEMENT

HEAVY DUTY CONCRETE PAVEMENT PER DETAIL

CONCRETE SIDEWALK PER DETAIL

CODED NOTES

PROPOSED PARKING SPACES

BUILDING IDENTIFICATION COGO POINT

DECORATIVE FENCE

HANDI-CAP PARKING SYMBOL P.A.U.E PRIVATE ACCESS AND UTILITY EASEMENT

EMERGENCY FLOOD ROUTING

- 1. PRIVATE ACCESS DRIVE TO BE CONSTRUCTED AND MAINTAINED
- 2. A MINIMUM OF 10' OUTSIDE WALL TO OUTSIDE WALL MUST BE MAINTAINED BETWEEN PATIO HOMES.
- 3. UNLESS APPROVED OTHERWISE BY HSEU, FINAL PAD ELEVATIONS FOR LOTS IN THIS DEVELOPMENT CANNOT EXCEED THOSE SHOWN HEREON BY MORE THAT FIVE TENTHS (0.5) FOOT.

1 CONTRACTOR TO INSTALL FOUNTAINS IN DETENTION BASIN.

BUILDING LOCATION

2 CONTRACTOR TO INSTALL STOP SIGN (R1-1)


BLDG #	POINT A	POINT B
1	N: 1730501.96 E: 234855.28	N: 1730491.12 E: 234925.87
2	N: 1730488.81 E: 234940.71	N: 1730476.83 E: 235018.71
3	N: 1730476.12 E: 235041.93	N: 1730451.67 E: 235109.03
4	N: 1730435.03 E: 235136.92	N: 1730379.94 E: 235193.43
5	N: 1730369.48 E: 235204.18	N: 1730319.63 E: 235255.32
6	N: 1730276.25 E: 235313.47	N: 1730276.64 E: 235392.38
7	N: 1730276.69 E: 235402.38	N: 1730277.08 E: 235481.30
8	N: 1730271.47 E: 235494.79	N: 1730264.98 E: 235565.91
9	N: 1730097.57 E: 235649.07	N: 1730078.24 E: 235580.32
10	N: 1730074.30 E: 235554.52	N: 1730083.03 E: 235483.63
11	N: 1730085.54 E: 235473.87	N: 1730085.45 E: 235394.95
12	N: 1730085.43 E: 235384.95	N:1730085.34 E:235306.03
13	N: 1730102.98 E: 235237.02	N: 1730137.12 E: 235174.30
14	N:1730246.52 E:235069.44	N: 1730301.60 E: 235012.93
15	N: 1730296.61 E: 234995.61	N: 1730307.45 E: 234925.02
16	N: 1730310.06 E: 234907.99	N: 1730320.90 E: 234837.40

TRILOGY HEALTH
SERVICES, LLC.
303 N. HURSTBOURNE PARKWAY
CLITTE 200 LOUISVILLE, KY 40222


ATIO HOMES AT PRAIRIE LAKES NOBLESVILLE

PROJECT DATE: PROJECT NO.: T1730034 DRAWN BY: CHECKED BY:


SITE ELOPIV PLAN



OVERALL UTILITY PLA



NOT FOR CONSTRUCTION




E.S.

ATIO HOMES AT PRAIRIE LAKES NOBLESVILLE

PROJECT DATE:

PROJECT NO.: DRAWN BY: CHECKED BY:

OVERALL GRADING PLA






ATIO HOMES AT PRAIRIE LAKES NOBLESVILLE

PROJECT DATE: AUG 2024 PROJECT NO.: T1730034

DRAWN BY: CHECKED BY:



# LANDSCAPE PLAN NOTES

1. THE CONTRACTOR SHALL PROVIDE A ONE YEAR WARRANTY ON ALL PLANTS AND VEGETATION PROPOSED ON THE LANDSCAPING PLAN. ANY TREES, SHRUBS, GROUND COVER OR OTHER VEGETATION PLANTED AS PART OF THIS PROJECT THAT DO NOT SURVIVE ONE YEAR FROM PLANTING SHALL BE REPLACED AT THE EXPENSE OF THE CONTRACTOR.

2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING AND COORDINATING WITH ALL PERTINENT UTILITY COMPANIES THREE WORKING DAYS IN ADVANCE OF ANY DIGGING. THE CONTRACTOR SHALL ASSUME SOLE RESPONSIBILITY FOR ANY COST INCURRED DUE TO DAMAGE OF ANY

3. REFER TO THE LANDSCAPE PLAN FOR ADDITIONAL NOTES. LANDSCAPE IMPROVEMENTS SHALL CONFORM TO THE LATEST EDITION OF ODOT

4. ALL PLANTING MATERIALS: SHALL BE PLANTED PER ODOT SPECIFICATIONS. EXISTING TREES TO REMAIN SHALL BE PRUNED TO REMOVE BROKEN, LOW HANGING AND OTHER UNDESIRABLE GROWTH TO ENSURE HEALTHY AND SYMMETRICAL NEW GROWTH.

5. PLANTING BEDS. ONE MONTH BEFORE CULTIVATION AND AFTER DAYTIME TEMPERATURES HAVE WARMED TO 60° CONSISTENTLY, TREAT ALL PLANTING BEDS THAT ARE TO BE DEVELOPED IN AREAS OF EXISTING TURF WITH PRE-EMERGENT AND POST-EMERGENT TYPE HERBICIDES. USE A STATE-LICENSED PESTICIDE APPLICATOR TO APPLY THE HERBICIDE. REPEAT HERBICIDE APPLICATION TWO WEEKS LATER AND UNTIL ALL HERBACEOUS MATERIALS HAVE BEEN KILLED. BEFORE PLANTING. TOP DRESS ALL PLANTING BEDS WITH A MINIMUM OF 6 INCHES OF BACKFILL MIX, THEN CULTIVATE PLANTING AREA TO A DEPTH OF 6 INCHES USING A PLOW, DISC, OR ROTO-TILLER.

6. BACKFILL MIX. FOR ALL PLANTINGS, USE BACKFILL MIX CONSISTING OF THE FOLLOWING:

- A. ONE PART EXCAVATED SOIL.
- B. ONE PART TOPSOIL.
- C. ONE PART EPA RATED CLASS IV COMPOST.

D. A SLOW RELEASE COMMERCIAL FERTILIZER (0-20-20 OR EQUAL) ADDED AT A RATE OF 5 POUNDS PER CUBIC YARD TO THE BACKFILL MIX. E. IF SOIL AREAS ARE OF HIGH PH (GREATER THAN 6.5), APPLY 1.25 POUNDS OF ELEMENTAL SULFUR PER CUBIC YARD OF BACKFILL MIX. NOTE: CONTRACTOR SHALL SUPPLY A DETAILED SOIL ANALYSIS PRIOR TO ALL PLANT BED PREPARATION. ANALYSIS SHALL INDICATE SOIL PH, TEXTURE, MAJOR NUTRIENTS, SALTS, ETC. SOIL ANALYSIS SHALL BE FROM A REPUTABLE, INDEPENDENT LAB. SOIL AMENDMENTS SHALL BE INCORPORATED INTO BACKFILL/PLANT MIX AS RECOMMENDED BY THE INDEPENDENT LAB.

7. MULCH. SMOOTH AND SHAPE THE BACKFILL MIX TO FORM A SHALLOW BASIN SLIGHTLY LARGER THAN THE PLANTING HOLE. MULCH ALL PLANTING AREAS WITH A LAYER OF FINELY SHREDDED HARDWOOD BARK OF UNIFORM TEXTURE & SIZE. PLANTS GROUPED IN MASSES SHALL HAVE THE ENTIRE CONTIGUOUS PLANTING BED OR ISLAND MULCHED. USE SHREDDED HARDWOOD BARK AGED MIN. ONE YEAR. RAKE AND SMOOTH THE ENTIRE AREA OF THE PLANTING BEDS, MULCH TO A DEPTH OF 3 INCHES. AFTER MULCHING AND BEFORE WATERING, ADD A SLOW RELEASE COMMERCIAL FERTILIZER (12-12-12 OR EQUAL), IN GRANULAR FORM, TO THE TOP OF THE MULCH AT A RATE OF 5 POUNDS PER 1000 SQUARE FEET. DO NOT ALLOW FERTILIZER TO CONTACT THE STEMS, BRANCHES, ROOTS OR LEAVES.

8. PERIOD OF ESTABLISHMENT. BEFORE FINAL INSPECTION. PLACE ALL PLANTS. SEED ALL LAWNS. AND CARE FOR THEM FOR A PERIOD OF ESTABLISHMENT. THE PERIOD OF ESTABLISHMENT BEGINS IMMEDIATELY UPON COMPLETION OF THE PLANTING OPERATIONS AND CONTINUES UNTIL OCTOBER 1. THE MINIMUM PERIOD OF ESTABLISHMENT IS ONE GROWING SEASON, JUNE 1 THROUGH OCTOBER 1. DURING THE PERIOD OF ESTABLISHMENT, FOLLOW STANDARD HORTICULTURAL PRACTICES TO ENSURE THE VIGOR AND GROWTH OF THE TRANSPLANTED MATERIAL. WATER, REMULCH, RESTAKE, GUY, AND CULTIVATE AS NECESSARY. PERFORM AT LEAST TWO WEEDING AND MOWING PROGRAMS (AROUND TREES, GUY STAKES, SHRUBS, AND BED EDGES) OF SUCH INTENSITY AS TO COMPLETELY RID THE PLANTED AND MULCHED AREAS OF WEEDS AND GRASSES. BEGIN THE FIRST PROGRAM ON OR ABOUT JUNE 15 AND THE SECOND APPROXIMATELY 8 WEEKS LATER. ON OR ABOUT AUGUST 15, THE ENGINEER WILL INSPECT THE PLANTING AND SUPPLY THE CONTRACTOR WITH A LIST OF MISSING AND DEAD PLANTS AND THOSE THAT HAVE DIED BACK BEYOND NORMAL PRUNING LINES. REPLANT AS REQUIRED ACCORDING TO THE SPECIFICATIONS OF THE ORIGINAL MATERIAL. REPLACEMENT PLANTS ARE SUBJECT TO A NEW PERIOD OF ESTABLISHMENT. IMMEDIATELY REPLACE PLANTS PLANTED INITIALLY IN THE FALL THAT HAVE DIED BEFORE THE SPRING PLANTING SEASON. CARE FOR THE REPLACEMENT PLANTS DURING THE NEW ESTABLISHMENT PERIOD.

## 9. RESTORATION OF DISTURBED AREAS FOR NEW LAWN:

ALL DISTURBED AREAS NOT COVERED BY BUILDING, PAVEMENT OR LANDSCAPE PLANTING BEDS SHALL BE PREPARED FOR GRASS SEED AND SEEDED. LOOSEN RUTS AND WORK THE SOIL AREAS TO A MINIMUM OF 6" DEEP PRIOR TO FINE GRADING AND SEEDING WORK. AREAS TO RECEIVE GRASS SEED SHALL HAVE A MIN. 4" TOPSOIL PLACED, SEEDED AND A STRAW/MULCH BLANKET COVER PLACED OVER THE SEEDED AREAS PER ODOT SPECIFICATIONS. FERTILIZE WITH ONE POUND OF ACTUAL NITROGEN PER 1000 SQUARE FEET WITH A SLOW RELEASE COMMERCIAL STARTER FERTILIZER (LESCO 18-24-12 OR EQUAL).

# 10. LANDSCAPE TREES, SHRUBS AND PERENNIAL WATERING:

THE CONTRACTOR SHALL BE RESPONSIBLE FOR FURNISHING, DELIVERING, APPLYING, MEASURING AND SCHEDULING A SUFFICIENT AMOUNT OF WATER NECESSARY TO KEEP EACH PLANT IN A HEALTHY GROWING CONDITION THROUGHOUT THE PERIOD OF ESTABLISHMENT. THE CONTRACTOR SHALL APPLY 1" OF WATER PER WEEK TO ALL NEW PLANTS. THE CONTRACTOR SHALL INSTALL & MAINTAIN SUPPLEMENTAL DRIP WATERING TREE BAGS (SUCH AS 20 GALLON TREE GATOR WATER BAG) TO PROVIDE ADEQUATE, SLOW RELEASE OF WATER. WATER BAGS SHALL BE REMOVED AT THE END OF THE SECOND GROWING SEASON.


# 11. TURF GROUNDCOVER (SODDING, SEEDING AND SEED MULCHING):

ALL SEEDING INSTALLATION SHALL CONFORM TO ODOT SPECIFICATIONS AND NOTE 9 ABOVE. SEED AT 6 LBS/1000 SF WITH THE FOLLOWING SEED MIXTURE:

TITAN TALL-TYPE TURF FESCUE SR 4100 PERENNIAL RYEGRASS

MERIT KENTUCKY BLUEGRASS

70% 20% 10%




ALL SHRUBS PLANTED IN ROWS OR MASSES SHALL BE MATCHED IN SIZE AND FORM.


SHRUBS SHALL BEAR SAME RELATION TO FINISH GRADE AS THEY BORE TO EXISTING GRADE IN THE PREVIOUSLY PLANTED CONDITION.

# MASS SHRUB PLANTING DETAIL (B&B OR CONTAINER)

NO SCALE




# DECIDUOUS TREE PLANTING DETAIL



LANDSCAPE DETAIL - PARKING LOT

SCALE: 1"=10'



LANDSCAPE DETAIL - CLUBHOUSE

SCALE: 1"=10'

Ĭ.

ATIO HOMES AT PRAIRIE LAKES NOBLESVILLE

PROJECT DATE: PROJECT NO.:

DRAWN BY: CHECKED BY:

NOTES & DETAILS

NOTES

