



**NOBLESVILLE FIRE DEPARTMENT**  
**FIRE PREVENTION BUREAU**  
**INSPECTION DIVISION**  
MATT MITCHELL – DIVISION CHIEF  
DARREL CROSS – FIRE INSPECTOR  
RYAN FLORA – PT FIRE INSPECTOR



## **RESIDENTIAL PRE-CONSTRUCTION MEETING**

- All fire hydrants shall be installed, functional, and approved by this office, prior to the issuance of any building permits.
- Fire apparatus access roads (*including temporary turnarounds between phases*) shall be installed and made serviceable prior to the issuance of any building permits.
- Temporary street signs shall be installed at each street intersection when construction of new roadways allows passage by vehicles. Signs shall be of an approved size, weather resistant and be maintained until replaced by permanent signs.
- During and after construction, the fire department shall not be deterred or hindered from gaining immediate access to fire hydrants.
- During and after construction, fire apparatus access roads shall not be obstructed in any manner, including the parking of vehicles. All apparatus access roads shall have an unobstructed width of 20 feet at all times.
- Please contact this office upon completing all fire hydrant installations for inspection and approval.

Matt Mitchell  
Division Chief / Fire Marshal  
(317) 776-6336 Ext. 1412  
[mmitchell@noblesville.in.us](mailto:mmitchell@noblesville.in.us)