

Addendum No. 1 BlueSky Early Action Utility Relocation and Grading – EN-244

August 4, 2015

<u>Item #1 – Pre-Bid Meeting Summary</u>

INSERT the attached Meeting Summary for Pre-Bid Meeting held on August 3, 2015.

Item #2 - Itemized Proposal

DELETE the Itemized Proposal and REPLACE with the attached Itemized Proposal.

Item #3 - Easement Legal Descriptions

The follow attached easement shall be staked for pay item "Easement Staking." Legal descriptions are attached.

- I. BlueSky Duke Easement
- II. Sunshine Investors (La Roca) Utility Easement
- III. Cole WY Portfolio II, LLC (Wendy's) Utility Easement
- IV. Federal Hill Commons Duke Easement
- V. Federal Hill Commons Utility Easement

Item #4 - Plan Sheets

DELETE pages C300, C400, C401, C500, C501, C601, and C602. Replace with attached pages C300, C400, C401A, C401B, C500, C501, C601, and C602.

<u>Item #5 – Indiana American Water Company Approved Contractors</u>

Attached is a list of contractors pre-qualified with Indiana American Water Company.

Item #6 - Work on SR32 (Paving, Backfill, and Maintaining Traffic)

Contractor or subcontractor performing backfilling and Maintaining Traffic work must be in good standing with INDOT, knowledge of INDOT standards, and have INDOT experience. Contractor or subcontractor performing paving work on SR32 must be INDOT pre-qualified for HMA paving and utilize asphalt from INDOT approved source.

Please acknowledge receipt of this Addendum by sending an email to jhellmann@noblesville.in.us

CITY OF NOBLESVILLE

James J. Hellmann, P.E.

PRE-BID MEETING SUMMARY

PROJECT NAME: BlueSky Early Action Grading and Utility Work – EN-244 **LOCATION:** Noblesville City Hall; 16 South 10th Street, Noblesville, IN 46060

DATE: August 3, 2015

TIME: 2:00 PM

I. Opening Comments / Introduction

Owner: City of Noblesville

Board of Public Works and Safety

16 South 10th Street Noblesville, IN 46060

Owner's Representative: Jim Hellmann, P.E.

City of Noblesville – Department of Engineering

Phone: (317) 776-6330, Email: jhellmann@noblesville.in.us

Attendee Company
John Simpson Monroe, LLC
Jerry Watson Daystar Drilling

Brittany Heidenreich American Structurepoint

John Beery City Engineer
Jim Hellmann Asst City Engineer

II. Project Description

The work consists of the installation of new water main; sanitary sewer manhole work with approximately 50 feet of 6" PVC lateral; the installation of conduit and duct work for the future use and the installation of fiber and communications utilities by others; and, the completion of preliminary grading work as shown on the plans.

Purpose of work is to allow the relocation and extension of utilities for the BlueSky and Federal Hill Commons projects. Some existing infrastructure is on poles which will be placed underground. Grading is to allow transformers, switchgear, or similar to be placed at the future finished grade.

III. Dates

- A. Bid opening -August 11, 2015
 - i. Proposals opened 9:00 AM, Due 8:30 AM
- B. Anticipated Award –August 25, 2015
- C. Anticipated Notice to Proceed dates
 - i. Partial: August 31, 2015: Notice to Proceed is anticipated to be given for the earthwork for the BlueSky site, conduit work adjacent to BlueSky site, sewer work, easement staking, and conduit work on Federal Hill Commons
 - ii. Remaining: Anticipated on September 21, 2015
- D. Completion
 - i. Earthwork on BlueSky: September 26, 2015
 - ii. Conduit installation: October 17, 2015
 - iii. All Work: October 31, 2015

IV. Bonds

A. Bidding:

Bid Bond (5% of submitted bid)

B. Awarded Contractor

Payment Bond (100% of contract amount)
Performance Bond (100% of contract amount)

V. Examination of the Site

Each bidder has a duty to examine the site of the work to fully inform themselves of the all the

existing and surrounding conditions of the site.

VI. Discussion

Pre-Bid meeting is not mandatory, but the meeting summary to be provided to all plan holders.

Bidder must be an official plan holder to bid on project.

Conduit will not be installed up Nixon Street and a bore will be required under Logan Street.

Questions are due August 4, 2015. Questions can be posed in writing after that, but may or may not be responded to. If question is significant, it will be responded to and distributed to <u>all</u> plan holders.

Advised that Addendum #1 will have additional conduit details, pipe only riser locations, and the tap on the watermain under SR32 will need to be removed at the main. Sheets C400, C401, and C500 will be updated accordingly and distributed.

Boring of 4" PVC Sch will be switched to 4" HDPE DR 17 and updated via addendum.

Risers will be pipes only, no structure.

___ 8/4/2015

Watermain pipe classification will be C900 DR18. Watermain to have 54 inches of cover. Backfill of watermain shall be included in the cost of the water main. Backfill shall be INDOT structure backfill, not sand or B-Borrow. Structure backfill must meet INDOT graduation requirements.

Watermain work must be installed by a pre-approved contractor with Indiana American Water Company (IAWC). Questions regarding pre-approval must be directed to IAWC. City to check if IAWC pre-approved list can be distributed.

Meeting adjourned at 2:20 PM.

Minutes are interpretation of meeting by undersigned. Any questions or corrections should be directed to Jim Hellmann at jhellmann@noblesville.in.us.

Jim Hellmann, P.E.

City of Noblesville

BlueSky Early Action Utility and Grading EN-244

ITEMIZED PROPOSAL

Item No.	Description	Quantities	Unit	Unit Price	Extended Price
item No.	Construction Engineering		LSUM	Offic Price	Extended Frice
2	Mobilization and Demobilization		LSUM		
3	Clearing		LSUM		
4	Maintaining Traffic	1	LSUM		
5	Easement Staking	2	EA		
6	Excavation, Common	1,125	CY		
7	HMA Surface, Type C	41	TON		
8	HMA Int, Type B	170	TON		
9	Mobilization and Demobilization for Seeding	2	EACH		
10	Seeding and Restoration, U	1,690	SY		
11	Erosion Control Blanket	1,640	SY		
12	Inlet Protection		EACH		
13	Silt Fence	1,340	LFT		
<u>14</u>	<u>Fiber Roll</u>		<u>LFT</u>		
<u>15</u>	Conduit, HDPE, 2 inch, DR-11	1,690	LFT		
<u>16</u>	Conduit, HDPE, 1.5 inch, DR-11		LFT		
<u>17</u>	Conduit, HDPE, 1.25 inch, DR-11	<u>3,900</u>			
<u>18</u>	Conduit, HDPE, 4 inch, DR-17	<u>1,920</u>			
<u>19</u>	Pipe, C900 DR18, 8 inch, Water Main	325	LFT		
<u>20</u>	Pipe, C900 DR18, 6 inch capped future connection with T				
	<u>and valve</u>		<u>LFT</u>		
<u>21</u>	11.25 Degree Bend for C900		EA		
<u>22</u>	8 Inch Cast Iron Water Tap <u>w/ Value</u>		EA		
<u>23</u>	8 Inch to 6 Inch Water Reducer		EA		
<u>24</u>	Fire Hydrant Assembly		EA		
<u>25</u>	Pipe, PVC, Circular, 6 inch, SDR-26 (w/ core)		LFT		
<u>26</u>	Manhole, Adjust to Grade		EA		
<u>27</u>	#2 Stone, Construction Entrance (Undistributed)		TON		
<u>28</u>	Retire Former Water Tap under SR32	<u>1</u>	<u>EA</u>		

	Total Estimated Construction Costs =	\$ -
CONTRACTOR:		
ADDRESS:		
-		
TELEPHONE:		
FAX:		
CONTACT:		
EMAIL:		

EDIT

EXHIBIT "A"

CITY OF NOBLESVILLE

PERMANENT UTILITY EASEMENT

Project: BlueSky Headquarters

Parcel: 5

Part of Lot 1 in Square 3 of West Noblesville, Hamilton County, Indiana, as per plat thereof, recorded in Deed Record 17, page 209, in the Office of the Recorder of Hamilton County, Indiana, a part of Osborn Street (to be vacated) and a part of Lot 9 of West Noblesville Square 2, as per plat thereof recorded in Plat Cabinet 3, Slide 567 in said Office of the Recorder, described as follows: Beginning at the northeast corner of said Lot 9; thence along the easterly and southerly lines of said Lot 9 the following six (6) courses: 1) South 00 degrees 32 minutes 11 seconds West 257.57 feet; 2) North 89 degrees 27 minutes 49 seconds West 2.09 feet; 3) South 56 degrees 40 minutes 40 seconds West 9.84 feet; 4) North 89 degrees 55 minutes 57 seconds West 102.76 feet; 5) North 59 degrees 46 minutes 21 seconds West 19.74 feet; 6) North 82 degrees 19 minutes 23 seconds West 5.00 feet; thence North 18 degrees 57 minutes 08 seconds East 15.30 feet; thence South 82 degrees 19 minutes 23 seconds East 5.00 feet; thence South 59 degrees 46 minutes 21 seconds East 18.69 feet; thence South 89 degrees 55 minutes 57 seconds East 94.10 feet; thence North 00 degrees 32 minutes 11 seconds East 336.26 feet; thence North 06 degrees 25 minutes 29 seconds West 75.27 feet to the southerly boundary of Logan Street; thence along said south boundary southeasterly 17.03 feet along an arc to the left having a radius of 1,081.74 feet and subtended by a long chord having a bearing of South 68 degrees 08 minutes 06 seconds East and a length of 17.03 feet to the west boundary of John Street; thence along said west boundary the following two (2) courses: 1) South 06 degrees 25 minutes 29 seconds East 68.11 feet; 2) South 00 degrees 32 minutes 11 seconds West 89.08 feet along/to to the point of beginning and containing 0.186 acres, more or less.

This description was prepared for the City of Noblesville, Indiana by Tracy L. McGill, Indiana Registered Land Surveyor, License Number 20500009, on the 21st day July, 2015.

ZCM'S.




EXHIBIT-"A"

STRUCTUREPOINT INC.

7260 SHADELAND STATION INDIANAPOLIS, IN 46256-3957 TEL 317.547.5580 FAX 317.543.0270 www.structurepoint.com DATE: 7/21/2015 SHEET NO.

DRAWN BY: TLM of

JOB NO. 14-2717



EDIT

EXHIBIT "A"

SUNSHINE INVESTORS Inst. No. 200500018048 &Inst. No. 200600029972

PERMANENT UTILITY EASEMENT

Project: BlueSky Headquarters

Parcel: 3

Key No.'s: 11-06-36-04-02-019.000; 11-06-36-04-02-020.000; 11-06-36-04-02-021.000

11-06-36-04-02-022.000

Part of Lots 2, 3 and 4 and part of the north south vacated alley adjacent to said Lots 2 & 3, all in Square 1 of West Noblesville, Hamilton County, Indiana, as per plat thereof, recorded in Deed Record 17, page 209, in the Office of the Recorder of Hamilton County, Indiana described as follows: Commencing at the southeast corner of said Lot 4; thence North 00 degrees 32 minutes 11 seconds East (assumed) 10.35 feet along the east line of said Lot 4 to a point on the northern boundary of State Road 32 and the **Point of Beginning** of this description: thence westerly 40.52 feet along an arc to the left having a radius of 1,679.02 feet and subtended by a long chord having a bearing of North 87 degrees 05 minutes 39 seconds West and a length of 40.52 feet to the eastern boundary of John Street; thence North 16 degrees 57 minutes 46 seconds West 21.16 feet along said east boundary; thence easterly 149.25 feet along an arc to the right having a radius of 1,699.02 feet and subtended by a long chord having a bearing of South 85 degrees 30 minutes 11 seconds East and a length of 149.20 feet to east line of that 0.95 acre parcel described in the Warranty Deed recorded as Instrument Number 200500018048 in said Office of the Recorder; thence South 00 degrees 32 minutes 11 seconds West 20.13 feet along said east line to the aforementioned northern boundary of State Road 32; thence along said northern boundary, westerly 102.37 feet along an arc to the left having a radius of 1,679.02 feet and subtended by a long chord having a bearing of North 84 degrees 39 minutes 21 seconds West and a length of 102.36 feet to the point of beginning and

This description was prepared for the City of Noblesville,
Indiana by Tracy L. McGill, Indiana Registered Land
Surveyor, License Number 20500009

July, 2015. This description was prepared for the Indiana by Tracy L. McGill, Indiana Registered Language Surveyor, License Number 20500009, on the 16th day

ZCM.S.

EXHIBIT-"A"


AMERICAN STRUCTUREPOINT

7260 SHADELAND STATION **INDIANAPOLIS, IN 46256-3957** TEL 317.547.5580 FAX 317.543.0270 www.structurepoint.com DATE: 7/16/2015 DRAWN BY: TLM

SHEET NO. of

2

JOB NO. 14-2717



EDIT

EXHIBIT "A"

Cole WY Portfolio II, LLC Inst. No. 2013010764 & Inst. No. 2013030538

PERMANENT UTILITY EASEMENT

Project: BlueSky Headquarters

Parcel: 4

Key No.: 11-06-36-04-02-025.000

Part of Lots 1 & 2 in Square 1 of West Noblesville, Hamilton County, Indiana, as per plat thereof, recorded in Deed Record 17, page 209, in the Office of the Recorder of Hamilton County, Indiana described as follows: Commencing at the southeast corner of said Lot 1; thence North 89 degrees 06 minutes 37 seconds West (assumed) 27.21 feet along the south line of said Lot 1 to the point of beginning of this description: thence continuing along said south line and the north boundary of State Road 32, North 89 degrees 06 minutes 37 seconds West 48.63 feet; thence continuing along the north boundary of said State Road 32, westerly 24.29 feet along an arc to the left having a radius of 1,679.02 feet and subtended by a long chord having a bearing of North 83 degrees 26 minutes 27 seconds West and a length of 24.29 feet to the southwest corner of Parcel I as described in General Warranty Deed recorded as Instrument Number 2013010764 in said Office of the Recorder; thence North 00 degrees 32 minutes 11 seconds East 20.10 feet along the west line of said Parcel I; thence easterly 25.48 feet along an arc to the right having a radius of 1,699.02 feet and subtended by a long chord having a bearing of South 83 degrees 29 minutes 31 seconds East and a length of 25.48 feet; thence South 89 degrees 06 minutes 37 seconds East 53.46 feet to the east line of said Parcel I; thence South 17 degrees 18 minutes 17 seconds West 20.85 feet along said east line to the point of beginning and containing 0.035 acres, more or less.

This description was prepared for the City of Noblesville, Indiana by Tracy L. McGill, Indiana Registered Land Surveyor, License Number 20500009, on the 16th day July, 2015.






EXHIBIT-"A"

STRUCTUREPOINT INC.

7260 SHADELAND STATION INDIANAPOLIS, IN 46256-3957 TEL 317.547.5580 FAX 317.543.0270 www.structurepoint.com DATE: 7/16/2015

DRAWN BY: TLM


SHEET NO.

1

of

2

JOB NO. 14-2717



EXHIBIT

PART OF THE S.E. QUARTER, SECTION 36, TOWNSHIP 19 NORTH, RANGE 4 EAST NOBLESVILLE TOWNSHIP, HAMILTON COUNTY, INDIANA

LAND DESCRIPTION

A PART OF THE SOUTHEAST QUARTER OF SECTION 36, TOWNSHIP 19 NORTH, RANGE 4 EAST IN NOBLESVILLE TOWNSHIP, HAMILTON COUNTY, INDIANA DESCRIBED AS FOLLOWS:

COMMENCING AT THE NORTHWEST CORNER OF THE SOUTHEAST QUARTER OF SECTION 36, TOWNSHIP 19 NORTH, RANGE 4 EAST; THENCE SOUTH 00 DEGREES 18 MINUTES 55 SECONDS WEST (ASSUMED BEARING) 1346.81 FEET TO THE SOUTHWEST CORNER OF THE NORTH HALF OF SAID SOUTHEAST QUARTER; THENCE SOUTH 00 DEGREES 52 MINUTES 25 SECONDS WEST 66.00 FEET TO A P.K. NAIL AT THE INTERSECTION OF THE CENTER LINE OF LAKEVIEW DRIVE AND THE CENTERLINE OF S.R. 32; THENCE ON THE CENTER LINE OF SAID STATE ROAD 32 SOUTH 89 DEGREES 56 MINUTES 39 SECONDS EAST 940.89 FEET TO THE EXTENSION OF THE EAST RIGHT OF WAY LINE OF NIXON STREET; THENCE ON SAID EXTENSION OF THE EAST RIGHT WAY LINE OF NIXON STREET NORTH 00 DEGREES 39 MINUTES 02 SECONDS EAST 5.79 FEET TO THE POINT OF BEGINNING TO THIS DESCRIPTION;

THENCE CONTINUING ON SAID EAST RIGHT OF WAY LINE OF NIXON STREET THE FOLLOWING FOUR COURSES: 1) NORTH 00 DEGREES 39 MINUTES 02 SECONDS EAST 160.38 FEET; 2) THENCE NORTH 01 DEGREES 41 MINUTES 39 SECONDS EAST 185.32 FEET; 3) THENCE NORTH 12 DEGREES 48 MINUTES 14 SECONDS EAST 25.50 FEET; 4) THENCE NORTH 40 DEGREES 07 MINUTES 28 SECONDS EAST 16.23 FEET; THENCE SOUTH 01 DEGREES 41 MINUTES 39 SECONDS WEST 222.92 FEET; THENCE SOUTH 00 DEGREES 39 MINUTES 02 SECONDS WEST 20.23 FEET; THENCE SOUTH 89 DEGREES 30 MINUTES 00 SECONDS EAST 5.00 FEET; THENCE SOUTH 00 DEGREES 39 MINUTES 02 SECONDS WEST 128.56 FEET TO A CURVE WITH A RADIUS OF 1716.43 FEET AND A CENTRAL ANGLE OF 15 DEGREES 53 MINUTES 45 SECONDS; THENCE ON THE ARC OF SAID CURVE 476.20 FEET, SAID CURVE SUBTEND BY A CHORD BEARING SOUTH 70 DEGREES 18 MINUTES 59 SECONDS EAST 474.67 FEET TO A REVERUS CURVE WITH A RADIUS OF 38.52 FEET AND A CENTRAL ANGLE OF 55 DEGREES 29 MINUTES 03 SECONDS; THENCE ON THE ARC OF SAID CURVE 37.30 FEET, SAID CURVE SUBTEND BY A CHORD BEARING SOUTH 85 DEGREES 26 MINUTES 18 SECONDS EAST 35.86 FEET; THENCE NORTH 66 DEGREES 28 MINUTES 48 SECONDS EAST 210.01 FEET; THENCE NORTH 62 DEGREES 02 MINUTES 42 SECONDS EAST 76.65 FEET; THENCE NORTH 03 DEGREES 25 MINUTES 13 SECONDS EAST 54.09 FEET TO THE SOUTH LINE OF THE TRACT OF REAL ESTATE DESCRIBED IN INSTRUMENT No. 2013-3764; THENCE ON SAID SOUTH LINE NORTH 80 DEGREES 14 MINUTES 44 SECONDS EAST 25.68 FEET; THENCE SOUTH 03 DEGREES 25 MINUTES 13 SECONDS WEST 62.27 FEET; THENCE SOUTH 62 DEGREES 02 MINUTES 42 SECONDS WEST 97.36 FEET; THENCE SOUTH 66 DEGREES 28 MINUTES 48 SECONDS WEST 210.63 FEET TO A CURVE WITH A RADIUS OF 53.52 FEET AND A CENTRAL ANGLE OF 54 DEGREES 49 MINUTES 31 SECONDS; THENCE ON THE ARC OF SAID CURVE 51.21 FEET, SAID CURVE SUBTEND BY A CHORD BEARING NORTH 85 DEGREES 49 MINUTES 09 SECONDS WEST 49.28 FEET TO A REVURSE CURVE WITH A RADIUS OF 1701.43 FEET AND A CENTRAL ANGLE OF 16 DEGREES 27 MINUTES 50 SECONDS; THENCE ON THE ARC OF SAID CURVE 488.90 FEET, SAID CURVE SUBTEND BY A CHORD BEARING NORTH 70 DEGREES 37 MINUTES 09 SECONDS WEST 487.22 FEET TO THE POINT OF BEGINNING, CONTAIING 1.25 ACRES, MORE OR LESS.

"THE WITHIN LAND DESCRIPTION AND/OR EXHIBIT DRAWING WAS PREPARED BASED UPON RECORD INFORMATION AND/OR PRIOR SURVEYS OF THE PARENT TRACT. NO FIELD SURVEY WAS PERFORMED AND NO MONUMENTS WERE SET WITH THIS THIS LAND DESCRIPTION IS SUBJECT TO CHANGE BASED UPON A REVIEW OF A CURRENT BOUNDARY SURVEY OF THE PREMISES.

THIS SURVEY IS NOT COMPLETE AND/OR VALID WITHOUT BOTH PAGES.





7/23/15 DATE:



MILLER SURVEYING INC.

948 CONNER STREET

NOBLESVILLE INDIANA 46060

PH. # (317) 773-2644 FAX 773-2694


LOCATION: PART OF THE S.E. QUARTER, SECTION 36, T19N, R4E NOBLESVILLE TOWNSHIP, HAMILTON COUNTY, INDIANA DRAWN BY: MJJ PREPARED BY: KNA 1" = 100' FIELD BOOK: N/A SCALE: DATF: 7-23-15 PAGE: N/A JOB NUMBER SURVEY 4 FILE: N/A

B36095

FIELD WORK COMPLETED: N/A CLIENT: CITY OF NOBLESVILLE ENG. DESCRIPTION: EXHIBIT SURVEY Addendum 1 - EN-244 - Page 11 of 25







EXHIBIT

PART OF THE S.E. QUARTER, SECTION 36, TOWNSHIP 19 NORTH, RANGE 4 EAST NOBLESVILLE TOWNSHIP, HAMILTON COUNTY, INDIANA

LAND DESCRIPTION

DESCRIPTION OF EASEMENT

A PART OF THE SOUTHEAST QUARTER OF SECTION 36, TOWNSHIP 19 NORTH, RANGE 4 EAST IN NOBLESVILLE TOWNSHIP, HAMILTON COUNTY, INDIANA DESCRIBED AS FOLLOWS:

COMMENCING AT THE NORTHWEST CORNER OF THE SOUTHEAST QUARTER OF SECTION 36, TOWNSHIP 19 NORTH, RANGE 4 EAST; THENCE SOUTH 00 DEGREES 18 MINUTES 55 SECONDS WEST (ASSUMED BEARING) 1346.81 FEET TO THE SOUTHWEST CORNER OF THE NORTH HALF OF SAID SOUTHEAST QUARTER; THENCE SOUTH 00 DEGREES 52 MINUTES 25 SECONDS WEST 66.00 FEET TO A P.K. NAIL AT THE INTERSECTION OF THE CENTER LINE OF LAKEVIEW DRIVE AND THE CENTERLINE OF S.R. 32; THENCE ON THE CENTER LINE OF SAID STATE ROAD 32 SOUTH 89 DEGREES 56 MINUTES 39 SECONDS EAST 940.89 FEET TO THE EXTENSION OF THE EAST RIGHT OF WAY LINE OF NIXON STREET; THENCE ON SAID EXTENSION OF THE EAST RIGHT OF WAY LINE OF NIXON STREET NORTH 00 DEGREES 39 MINUTES 02 SECONDS EAST 5.79 FEET TO THE POINT OF BEGINNING TO THIS DESCRIPTION;

THENCE CONTINUING ON SAID EAST RIGHT OF WAY LINE OF NIXON STREET NORTH 00 DEGREES 39 MINUTES 02 SECONDS EAST 46.02 FEET; THENCE SOUTH89 DEGREES 06 MINUTES 37 SECONDS EAST 20.00 FEET; THENCE SOUTH 00 DEGREES 39 MINUTES 02 SECONDS WEST 24.29 FEET TO A CURVE WITH A RADIUS OF 1726.43 FEET AND A CENTRAL ANGLE OF 15 DEGREES 58 MINUTES 32 SECONDS; THENCE ON THE ARC OF SAID CURVE 481.37 FEET, SAID CURVE SUBTEND BY A CHORD BEARING SOUTH 70 DEGREES 20 MINUTES 35 SECONDS EAST 479.73 FEET TO A REVERSE CURVE WITH A RADIUS OF 28.52 FEET AND A CENTRAL ANGLE OF 56 DEGREES 11 MINUTES 10 SECONDS; THENCE ON THE ARC OF SAID CURVE 27.96 FEET, SAID CURVE SUBTEND BY A CHORD BEARING SOUTH 84 DEGREES 57 MINUTES 40 SECONDS EAST 26.94 FEET; THENCE NORTH 66 DEGREES 28 MINUTES 48 SECONDS EAST 209.59 FEET; THENCE NORTH 62 DEGREES 02 MINUTES 42 SECONDS EAST 82.36 FEET; THENCE NORTH 03 DEGREES 25 MINUTES 13 SECONDS EAST 42.38 FEET TO THE SOUTH LINE OF THE TRACT OF REAL ESTATE DESCRIBE IN INSTRUMENT No. 2013—37364; THENCE ON SAID SOUTH LINE NORTH 80 DEGREES 14 MINUTES 44 SECONDS EAST 25.68 FEET; THENCE SOUTH 03 DEGREES 25 MINUTES 13 SECONDS EAST DESCRIBE IN INSTRUMENT No. 2013—37364; THENCE ON SAID SOUTH LINE NORTH 80 DEGREES 14 MINUTES 44 SECONDS EAST 25.68 FEET; THENCE SOUTH 03 DEGREES 25 MINUTES 13 SECONDS EAST 62.27 FEET; THENCE SOUTH 62 DEGREES 02 MINUTES 42 SECONDS WEST 97.36 FEET; THENCE NORTH 25 DEGREES 44 MINUTES 15 SECONDS WEST 15.01 FEET; THENCE SOUTH 66 DEGREES 28 MINUTES 48 SECONDS WEST 210.01 FEET TO A CURVE WITH A RADIUS OF 38.52 FEET AND A CENTRAL ANGLE OF 55 DEGREES 29 MINUTES 03 SECONDS; THENCE ON THE ARC OF SAID CURVE 37.30 FEET, SAID CURVE SUBTEND BY A CHORD BEARING NORTH 85 DEGREES 26 MINUTES 18 SECONDS WEST 35.86 FEET TO A REVERSE CURVE WITH A RADIUS OF 1716.43 FEET AND A CENTRAL ANGLE OF 15 DEGREES 53 MINUTES 45 SECONDS; THENCE ON THE ARC OF SAID CURVE 476.20 FEET, SAID CURVE SUBTEND BY A CHORD BEARING NORTH 72 DEGREES 04 MINUTES 44 SECONDS WEST 469.91 FEET; THENCE SOUTH 00 DEGREES 39 MINUTES 02 SECONDS WEST 15.29 FEET TO A CURVE WITH A RADIUS OF 1701.43 FEET AND A CENTRAL ANGLE OF 0 DEGREES 41 MINUTES 09 SECONDS; THENCE ON THE ARC OF SAID CURVE 20.36 FEET, SAID CURVE SUBTEND BY A CHORD BEARING NORTH 78 DEGREES 30 MINUTES 30 SECONDS WEST 20.36 FEET TO THE POINT OF BEGINNING, CONTAINING 0.27 ACRES, MORE OR LESS.

"THE WITHIN LAND DESCRIPTION AND/OR EXHIBIT DRAWING WAS PREPARED BASED UPON RECORD INFORMATION AND/OR PRIOR SURVEYS OF THE PARENT TRACT. NO FIELD SURVEY WAS PERFORMED AND NO MONUMENTS WERE SET WITH THIS THIS LAND DESCRIPTION IS SUBJECT TO CHANGE BASED UPON A REVIEW OF A CURRENT BOUNDARY SURVEY OF THE PREMISES.

THIS SURVEY IS NOT COMPLETE AND/OR VALID WITHOUT BOTH PAGES.

PAGE 2 OF 2

No. LS20400007 TO STATE OF WOLANA SURVENIENT OF SURVENIENT LS20400007

7/23/15 DATE:





MILLER SURVEYING INC. 948 CONNER STREET NOBLESVILLE INDIANA 46060 PH. # (317) 773-2644 FAX 773-2694


(s
	1	
RED	BY:	K١

M

LOCATION: PART OF THE S.E. QUARTER, SECTION 36, T19N, R4E NOBLESVILLE TOWNSHIP, HAMILTON COUNTY, INDIANA DRAWN BY: MJJ PREPAR SCALE: 1" = 100' FIELD BOOK: N/A FIELD WORK COMPLETED: N/A
CLIENT: CITY OF NOBLESVILLE ENG.
DESCRIPTION: EXHIBIT SURVEY DATE: 7-23-15 PAGE: N/A SURVEY 4 FILE: JOB NUMBER B36095 N/A







EXISTING LEGEND



TER VALVE OF RIM ELEVATION VERT ELEVATION

LASTIC PIPE
EINFORCED CONCRETE PIPE
DRRUGATED METAL PIPE 7260 Shadeland Station | Indianapolis, Indiana 46256 TEL 317.547.5580 | FAX 317.543.0270 www.structurepoint.com

PROPOSED GRADING LEGEND

M.E.	MATCH EXISTING
000	CONTOURS
000.00	SPOT ELEVATIONS

CAUTION !!

CONSTRUCTION.

THE LOCATIONS OF ALL EXISTING UNDERGROUND UTILITIES SHOWN ON THIS PLAN ARE BASED UPON ABOVE GROUND

EVIDENCE (including, but not limited to, manholes, inlets,

valves, and marks made upon the ground by others) AND ARE SPECULATIVE IN NATURE. THERE MAY ALSO BE OTHER

EXISTING UNDERGROUND UTILITIES FOR WHICH THERE IS NO

EVIDENCE WAS OBSERVED. THE EXACT LOCATIONS OF SAID EXISTING UNDERGROUND UTILITIES SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO ANY AND ALL CONSTRUCTION.

ABOVE GROUND EVIDENCE OR FOR WHICH NO ABOVE GROUND

INDIANA UNDERGROUND –

CONTRACTOR SHALL PROTECT AND NOT DESTROY THE PROPERTY CORNER MONUMENTS DURING

. CONTRACTOR TO VERIFY LOCATION, SIZE AND DEPTH OF EXISTING UTILITIES PRIOR TO

COMMENCING ANY CONSTRUCTION. CONTACT

3. SEE ALL NOTES ON GENERAL NOTES SHEET 002.

ENGINEER IF VARIATION EXISTS.

GRADING TRANSITION LINE (SOUTH AND EAST OF LINE AT PROPOSED GRADES FOR UTILITY RELOCATION, NORTH AND WEST OF LINE TO TIE BACK TO EXISTING GRADE)

BLUE SKY EARLY ACTION UTILITY RELOCATION AND **GRADING PROJECT**

123 JOHN ST. NOBLESVILLE, IN



	ISSUANCE INDEX
DATE:	
07/24/2015	
PROJE	CT PHASE:
CONST	RUCTION DOCUMENTS

	REVISION SCHEDULE					
NO.	DESCRIPTION	DATE				
Λ	ADDENDUM #1	08/04/15				

Project Number 2014.02717

GRADING PLAN

(NAVD '88)

BM HM 34 BERNTSEN MONUMENT SET IN CASTING AT RIVERVIEW HOSPITAL, EAST OF THE MAIN ENTRANCE DRIVE, NORTHEAST OF THE HELIPORT AND SOUTHWEST OF PARKING LOT. ELEV - 787.87

REBAR SET IN GRASS, ±35' EAST AND ±45' SOUTH OF THE SW CORNER OF THE END OF THE WEST END OF ASPHALT OF OSBORN STREET.


ASI TBM #100 RAILROAD" SPIKE IN NE SIDE LIGHT POLE PSI#052-9 AT & OSBORN STREET; ±10' WEST OF THE WEST END OF PAVEMENT. ELEV - 792.11

RAILROAD" SPIKE NW SIDE LIGHT POLE AT NORTHWEST CORNER OF SR 32 AND JOHN STREET. ELEV - 766.72

ASI TBM #102 MAG SPIKE NE SIDE UTILITY POLE #69-892; SW

CORNER JOHN STREET AND LOGAN STREET. ELEV - 770.80

Addendum 1 - EN-244 - Page 15 of 25





7260 Shadeland Station | Indianapolis, Indiana 46256 TEL 317.547.5580 | FAX 317.543.0270 www.structurepoint.com

BLUE SKY EARLY
ACTION UTILITY
RELOCATION AND
GRADING PROJECT

123 JOHN ST. NOBLESVILLE, IN



	ISSUANCE INDEX		
DATE:			
07/24/2015			
PROJE	T PHASE:		
CONST	RUCTION DOCUMENTS		


	REVISION SCHEDULE					
NO.	DESCRIPTION	DATE				
\triangle	ADDENDUM #1	08/04/15				

Project Number

2014.02717

UTILITY PLAN






SECTION DETAIL Conduit Riser Conduit(s) Seal open end with duct tape with tracer wire accessable 3 Ft. (Typ.) Minimum radius per manufactures specifications

Conduit Group Summary Table						
Conduit Group	Pipe Dia. (in)	Qty	CL Length (ft)	Total Length (ft)	Notes	
•	2.00	1	210	210	In SR32 R/W	
С	1.25	2	210	420	III SK32 K/ W	
B (John St.)	1.50	1	590	590	In R/W	
B (Nixon St.)	1.50	1	400	400	In R/W, portion req'd to be bored	
	2.00	1	520	520	Mostly in easement, portions	
U	1.25	3	520	1560	req'd to be bored	
	2.00	1	960	960		
Z	1.25	2	960	1920	In easement, portions req'd to be bored	
	4.00	2	960	1920		

Material Summary Table				
Dia. (in)	Material	Class	Total Length Req'd (ft)	
1.25	HDPE	DR11	3,900	
1.50	HDPE	DR11	990	
2.00	HDPE	DR11	1,690	
4.00	HDPE	DR17	1,920	

General Notes

- 1. Contractor shall have a surveyor stake out the utility and Duke easements, structure 21, and structures 25 shown on the plans. Work to be paid for in Easement Staking.
- 2. Conduit not shown to be bored can be either bored or trenched in and backfilled with compacted B-borrow. Trench spoils shall be removed from the site. Cost of boring shall be included in the cost of the material pay item.
- 3. HDPE conduits shall be placed and bound together when installed.
- 4. Conduit group "Z" can be bored in two bores, but the (1) 2" HDPE and (2) 1.25" HDPE must be bored together and the (2) 4" HDPE must be bored together. All other conduit groups be bored together.
- 5. Conduit group shall be installed with a tracer wire for future locating.
- 6. Conduit to be 36 inches deep except where a specific elevation is provided.
- 7. HDPE minimum bend radius per the manufacturers specifications.
- 8. Cost of riser pipe to be included in the cost of the conduit pipe.
- 9. Backfill and spoil removal will not be paid for directly, but included in the cost of other items. This includes pavement, concrete, or similar material removal in areas where a bore is not dictated per the plans.
- 10. Riser is only the extention of pipe only. There is no installation of handhole, pedestal, or similar.



Bar = 1"





RECOMMENDED FOR APPROVAL		DUL_ N ENGINEER	8/4/15 DATE	
DESIGNED:	JJH	_ DRAWN:	JJH	
CHECKED.	IMP	CHECKED.	IMD	

	HORIZONTAL SCALE	BRIDGE	FILE
CITY OF NOBLESVILLE	N.T.S.	_	
DEPARTMENT OF ENGINEERING	VERTICAL SCALE	DESIGN	ATION
DEI MIVIMENT OF ENGINEERING	_	_	
	SURVEY BOOK	SHEE	TS
Early Action Site Utility & Grading	_	C401B of	_
Early Action Site Othicy & drading	CONTRACT	PROJ	ECT
	_	Bluesky	EAUG

PREPARED BY:


Department of Engineering 16 S. 10th Street, STE 155


www.cityofnoblesville.org\engineering

Noblesville, IN 46060

Ph: (317) 776-6330

Fax: (317) 776-6322






EXISTING LEGEND

<u> </u>	AIN CONDITIONEN		MOITI OF WAT MONOMENT
	BEEHIVE INLET	-	SIGN
6	BUSH	S	SANITARY MANHOLE
	CURB INLET	0	STAND PIPE
<u> </u>	CLEAN OUT	- O-	TELEPHONE POLE
ф ф	COMBINATION POLE	- T-	TELEPHONE PEDESTAL
		\boxtimes	TRANSFORMER
(DRAINAGE MANHOLE	£	TREE
	DOWN SPOUT	®	TRAFFIC MANHOLE
E	ELECTRIC METER BOX	®	WATER METER
©	GAS METER	wv	WATER WETER
<u>G</u>	GAS MARKER SIGN	\bowtie	WATER VALVE
.GV	0.4.0	tr	TOP OF RIM ELEVATION
\bowtie	GAS VALVE	inv	INVERT ELEVATION
<u> </u>	GUY WIRE	pvc	PLASTIC PIPE
\Rightarrow	LIGHT POLE	rcp	REINFORCED CONCRETE PIPE
<u> </u>	MAILBOX	cmp	CORRUGATED METAL PIPE
***	PINE	vcp hdpe	CLAY PIPE PLASTIC PIPE
•	POST	ohe	OVERHEAD ELECTRIC LINE
占	POWER POLE	g t	BURIED GAS LINE
		t	BURIED TELEPHONE LINE



7260 Shadeland Station | Indianapolis, Indiana 46256 TEL 317.547.5580 | FAX 317.543.0270 www.structurepoint.com

PROPOSED EROSION CONTROL LEGEND



SEEDING

– INDIANA UNDERGROUND –

CONTRACTOR SHALL PROTECT AND NOT DESTROY

THE PROPERTY CORNER MONUMENTS DURING

CONTRACTOR TO VERIFY LOCATION, SIZE AND

COMMENCING ANY CONSTRUCTION. CONTACT

3. SEE ALL NOTES ON GENERAL NOTES SHEET 002.

. POST-CONSTRUCTION WATER QUALITY MEASURES

WILL BE INCLUDED IN THE FINAL PROJECT.

DEPTH OF EXISTING UTILITIES PRIOR TO

ENGINEER IF VARIATION EXISTS.

CONSTRUCTION.

BLUE SKY EARLY ACTION UTILITY RELOCATION AND **GRADING PROJECT**

123 JOHN ST. NOBLESVILLE, IN



	ISSUANCE INDEX
DATE:	
07/24/20	015
PROJE	CT PHASE:
CONST	RUCTION DOCUMENTS

	REVISION SCHEDULE		
NO.	DESCRIPTION	DATE	
\triangle	ADDENDUM #1	08/04/15	

Project Number 2014.02717

EROSION CONTROL PLAN

ASI TBM #100 RAILROAD" SPIKE IN NE SIDE LIGHT POLE PSI#052-9 AT & OSBORN STREET; ±10' WEST OF THE WEST END OF PAVEMENT. ELEV - 792.11

RAILROAD" SPIKE NW SIDE LIGHT POLE AT NORTHWEST CORNER OF SR 32 AND JOHN STREET. | ELEV - 766.72

ASI TBM #102 MAG SPIKE NE SIDE UTILITY POLE #69-892; SW CORNER JOHN STREET AND LOGAN STREET. ELEV - 770.80

3. REPLACE THE STORM SEWER GRATE.

 REMOVE ACCUMULATED SEDIMENT AND DEBRIS AFTER EACH STORM EVENT. DEPOSIT SEDIMENT IN AN AREA WHERE IT WILL NOT RE-ENTER THE PAVED AREA OR STORM DRAINS. REPLACE OR CLEAN GEOTEXTILE FABRIC AS NEEDED.

WHEN THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED, REMOVE INLET PROTECTION.

DROP-IN INLET PROTECTION

• LIMITED TO ONE-QUARTER ACRE PER 100 LINEAR FEET OF BARRIER.

• FURTHER RESTRICTED BY SLOPE STEEPNESS. TABLE 1. FILTER SOCK SIZE REQUIREMENTS. SHEET FLOW APPLICATION

TABLE 1. FILTER SOCK SIZE REQUIREMENTS, SHEET FLOW AFFLICATION					
SLOPE		MAXIMUM DISTANCE ABOVE FILTER SOCK (LINEAR FEET) FOR MINIMUM FILTER SOCK SIZES (DIAMETER OF SOCK)			
		8 INCH	12 INCH	18 INCH	24 INCH
0%-2%	< 50:1	125	250	300	350
2%-10%	50:1 TO 10:1	100	125	200	250
10%-20%	10:1 TO 5:1	75	100	150	200
20%-33%	5:1 TO 3:1	25	50	75	100
>33%	>3:1	10	25	50	75

SLOPE APPLICATION

.. INSTALLED ON THE CONTOUR. • FIVE TO 10 FEET FROM TOE OF SLOPE (10 FEET PREFERRED).

CHANNEL/SWALE APPLICATION
 PERPENDICULAR TO CHANNEL FLOW.

•• LESS THAN ONE ACRE OF DRAINAGE AREA. •• UTILIZE LARGER PRODUCT, TYPICALLY 18 OR MORE INCHES.

ACCESSIBLE FOR MAINTENANCE (REMOVAL OF SEDIMENT AND REPLACEMENT IF NEEDED.

GEOTEXTILE FABRIC SOCK OR A NON-BIODEGRADABLE NETTING MATRIX.

SPECIFICATIONS FOR PERMEABLE MATERIAL:

 FEEDSTOCKS MAY INCLUDE, BUT ARE NOT LIMITED TO, WELL-COMPOSTED VEGETABLE MATTER, LEAVES, YARD TRIMMINGS, FOOD SCRAPS, COMPOSTED MANURES, PAPER FIBER, WOOD BARK, CLASS A BIOSOLIDS (AS DEFINED IN FEDERAL REGULATIONS 40 CFR 503 PART 503), OR ANY COMBINATION THEREOF.

 COMPOST SHALL BE PRODUCED USING AN AEROBIĆ COMPOSTING PROCESS MEETING CFR 503 REGULATIONS, INCLUDING TIME AND TEMPERATURE DATA INDICATING EFFECTIVE WEED SEED, PATHOGEN AND INSECT LARVAE

 COMPOST SHALL BE WELL DECOMPOSED, STABLE, AND WEED FREE.
 VARIABLE PARTICLE SIZE WITH MAXIMUM DIMENSIONS OF TWO INCHES IN LENGTH, ONE—HALF INCH IN WIDTH, AND ONE-HALF INCH IN DEPTH.

TABLE 2. COMPOST PARTICLE SIZE

PERCENT PASSING SIEVE SIZE			
2-INCH SIEVE	1-INCH SIEVE	3/4-INCH SIEVE	1/4-INCH SIEVE
100%	99%	70%	25%

- REFUSE FREE (LESS THAN ONE PERCENT BY WEIGHT).
 FREE OF ANY CONTAMINANTS AND MATERIALS TOXIC TO PLANT GROWTH.
- pH OF 5.5 TO 8.0 CARBON-NITROGEN RATIO NOT TO EXCEED 100. MOISTURE CONTENT NOT TO EXCEED 45 PERCENT BY DRY WEIGHT.

INERT MATERIALS NOT TO EXCEED ONE PERCENT BY DRY WEIGHT.

AGGREGATE SPECIFICATION

• INDOT CA NO. 5 OR NO. 8 AGGREGATE STRAW, EXCELSIOR, ETC. SPECIFICATION

PREMANUFACTURED.

POSTS - 2x2 INCH HARDWOOD OR STEEL POSTS

BONDING AGENTS (OPTIONAL)

PRODUCT INSTALLED.

TACKIFIERS, FLOCCULANTS, OR MICROBIAL ADDITIVES MAY BE USED TO REMOVE SEDIMENT AND/OR ADDITIONAL POLLUTANTS FROM STORM WATER RUNOFF. (ALL ADDITIVES COMBINED WITH COMPOST MATERIALS SHOULD BE TESTED FOR PHYSICAL RESULTS AT A CERTIFIED EROSION AND SEDIMENT CONTROL LABORATORY AND BIOLOGICALLY TESTED FOR ELEVATED BENEFICIAL MICROORGANISMS AT A UNITED STATES COMPOST COUNCIL, SEAL OF TESTING ASSURANCE APPROVED TESTING LABORATORY.)

DROP-IN INLET PROTECTION TO

BE USED IN PAVED AREAS.

INSTALLATION

1. LAY OUT THE LOCATION OF THE FILTER SOCK BARRIER SO THAT IT IS PARALLEL TO THE CONTOUR OF THE SLOPE AND AT LEAST 10 FEET BEYOND THE TOE OF THE SLOPE TO PROVIDE A SEDIMENT STORAGE AREA. TURN THE ENDS TO THE FILTER SOCK BARRIER UP SLOPE SUCH THAT THE POINT OF CONTACT BETWEEN THE GROUND AND THE BOTTOM OF THE FILTER SOCK BARRIER END TERMINATES AT A HIGHER ELEVATION THAN THE TOP OF THE FILTER SOCK BARRIER AT ITS LOWEST POINT.

2. EXCAVATE A TRENCH WITH A DEPTH AND WIDTH EQUAL TO AT LEAST ONE-FOURTH THE DIAMETER OF THE FILTER SOCK OR FOLLOW MANUFACTURER'S RECOMMENDATIONS. WHERE APPLICABLE, THE TRENCH MAY ALSO BE EXCAVATED UPSLOPE OF A CURB OR SIDEWALK. PLACING THE PRODUCT AGAINST THE CURB OR SIDEWALK

3. CONSTRUCT THE FILTER SOCK OR UTILIZE A PRE-MANUFACTURED PRODUCT. FOR COMPOST USE A PNEUMATIC BLOWER OR SIMILAR DEVICE TO PROVIDE ADEQUATE AND CONSISTENT FILL IN THE SOCK. (SEED OR SOD MAY

BE APPLIED AT THE TIME OF INSTALLATION FOR PERMANENT APPLICATIONS.)

4. IF MORE THAN ONE SOCK IS PLACED IN A ROW, THE SOCKS SHOULD BE OVERLAPPED; NOT ABUTTED.

5. ANCHOR THE FILTER SOCK BARRIER IN PLACE BY DRIVING POSTS THROUGH THE BARRIER AND INTO THE UNDERLYING SOIL MATERIAL. POSTS SHOULD BE SPACED NO MORE THAN FIVE FEET APART AND DRIVEN THROUGH THE MIDDLE OF THE SOCK. THE POSTS SHOULD BE DRIVEN A MINIMUM OF 18 INCHES DEEP IN TO THE SOIL. THE STAKE SHOULD BE FLUSH WITH THE TOP OF THE SOCK.


6. BACKFILL THE TRENCH WITH EXCAVATED SOIL PLACED AGAINST THE FILTER SOCK BARRIER TO GROUND LEVEL ON THE DOWN-SLOPE SIDE AND TO TWO INCHES ABOVE GROUND LEVEL ON THE UP-SLOPE SIDE OF THE FILTER SOCK BARRIER. COMPACT THE FILL MATERIAL TO KEEP IT IN PLACE.

MAINTENANCE


NISPECT WITHIN 24 HOURS OF A RAIN EVENT AND AT LEAST ONCE EVERY SEVEN CALENDAR DAYS. WHEN INSTALLED IN A SERIES AT INTERVALS ON A SLOPE, INSPECTION SHOULD BE DONE DAILY.

REMOVE ACCUMULATED SEDIMENT WHEN IT REACHES ONE-QUARTER THE HEIGHT OF THE FILTER SOCK. INSPECT TO ENSURE THAT THE SOCK IS MAINTAINING ITS INTEGRITY AND PRODUCING ADEQUATE FLOW. REPAIR ERODED AND DAMAGED AREAS. IF PONDING BECOMES EXCESSIVE, SOCKS SHOULD BE REMOVED AND EITHER RECONSTRUCTED OR NEW

RESEED, IF APPLICABLE . IF THE FILTER SOCK IS NOT DESIGNED AS A PERMANENT FILTER OR PART OF THE NATURAL LANDSCAPE AND THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED, USE A BLADE OR KNIFE TO CUT OPEN SOCK AND USE A BULLDOZER, LOADER, RAKE, OR OTHER DEVICE TO INCORPORATE THE ORGANIC MATERIAL INTO THE SOIL, OR SPREAD IT OVER THE TOP OF THE SOIL SURFACE FOR FINAL SEEDING. REMOVE AND DISPOSE OF SOCK IF NECESSARY.



FILTER TUBE / FILTER SOCK



 LIMITED TO ONE-QUARTER ACRE PER 100 LINEAR FEET OF FENCE. FURTHER RESTRICTED BY SLOPE STEEPNESS (SEE TABLE 1).

SIX MONTHS (MAXIMUM).

LOCATION INSTALLED PARALLEL TO THE SLOPE CONTOUR.

 MINIMUM OF 10 FEET BEYOND THE TOE OF THE SLOPE TO PROVIDE A BROAD, SHALLOW SEDIMENT POOL.

 ACCESSIBLE FOR MAINTENANCE (REMOVAL OF SEDIMENT AND SILT FENCE REPAIR).

SPACING TABLE 1. SLOPE STEEPNESS RESTRICTIONS

TABLE T. SLOPE	IABLE 1. SLUPE STEEPNESS RESTRICTIONS			
PERCENT SLOPE		MAXIMUM DISTANCE		
< 2%	< 50:1	100 FEET		
2% - 5%	50:1 TO 20:1	75 FEET		
5% – 10%*	20:1 TO 10:1	50 FEET		
10% - 20%*	10:1 TO 5:1	25 FEET		
> 20%	> 5:1	15 FEET		

*CONSIDER OTHER ALTERNATIVES. NOTE: MULTIPLE ROWS OF SILT FENCE ARE NOT RECOMMENDED ON THE SAME SLOPE.

DEPTH: EIGHT INCHES MINIMUM.

 WIDTH: FOUR INCHES MINIMUM. AFTER INSTALLING THE FENCE, BACKFILL WITH SOIL MATERIAL AND COMPACT (TO BURY AND ANCHOR THE LOWER PORTION OF THE


NOTE: AN ALTERNATIVE TO TRENCHING IS TO USE MECHANICAL EQUIPMENT TO PLOW IN THE SILT FENCE.

MATERIALS AND SILT FENCE SPECIFICATIONS FABRIC - WOVEN OR NON-WOVEN GEOTEXTILE FABRIC, MEETING

SPECIFIED MINIMUMS OUTLINED IN TABLE 2.

TABLE 2. GEOTEXTILE FABRIC SPECIFICATIONS FOR SILT FENCE (MINIMUM)				
PHYSICAL PROPERTY	WOVEN GEOTEXTILE FABRIC	NON-WOVEN GEOTEXTILE FABRIC		
FILTERING EFFICIENCY	85%	85%		
TEXTILE STRENGTH AT 20% ELONGATION STANDARD STRENGTH EXTRA STRENGTH	30 LBS. PER LINEAL INCH 50 LBS. PER LINEAL INCH	50 LBS. PER LINEAL INCH 70 LBS. PER LINEAL INCH		
SLURRY FLOW RATE	0.3 GAL./MIN./SQUARE FOOT	4.5 GAL./MIN./SQUARE FOOT		
WATER FLOW RATE	15 GAL./MIN./SQUARE FOOT	220 GAL./MIN./SQUARE FOOT		
UV RESISTANCE	70%	85%		
POST SPACING	7 FEET	5 FEET		

NOTE: SILT FENCES CAN BE PURCHASED COMMERCIALLY.



- HEIGHT A MINIMUM OF 18 INCHES ABOVE GROUND LEVEL (30 INCHES MAXIMUM). REINFORCEMENT FABRIC SECURELY FASTENED TO POSTS WITH WOOD LATHE.
- SUPPORT POSTS 2x2 INCH HARDWOOD POSTS. STEEL FENCE POSTS MAY BE SUBSTITUTED FOR HARDWOOD POSTS (STEEL POSTS SHOULD HAVE PROJECTIONS FOR FASTENING FABRIC).

 SPACING — EIGHT FEET MAXIMUM IS FENCE IS SUPPORTED BY WIRE MESH FENCING, SIX FEET MAXIMUM FOR EXTRA—STRENGTH FABRIC WITHOUT WIRE BACKING.

THE LOCATION OF THE FENCE SO THAT IS IS PARALLEL TO THE CONTOUR OF THE SLOPE AND

AT LEAST 10 FEET BEYOND THE TOE OF THE SLOPE TO PROVIDE A SEDIMENT STORAGE AREA. TURN THE ENDS OF THE FENCE UP SLOPE SUCH THAT THE POINT OF CONTACT BETWEEN THE GROUND AND THE BOTTOM OF THE FENCE END TERMINATES AT A HIGHER ELEVATION THAN THE TOP OF THE FENCE AT ITS

OWEST POINT. 2. EXCAVATE AN EIGHT-INCH DEEP BY FOUR-INCH WIDE TRENCH ALONG THE ENTIRE LENGTH OF THE FENCE

LINE. INSTALLATION BY PLOWING IS ALSO ACCEPTABLE. INSTALL THE SILT FENCE WITH THE FILTER FABRIC LOCATED ON THE UP-SLOPE SIDE OF THE EXCAVATED TRENCH AND THE SUPPORT POSTS ON THE DOWN-SLOPE SIDE OF THE TRENCH. . DRIVE THE SUPPORT POSTS AT LEAST 18 INCHES INTO THE GROUND, TIGHTLY STRETCHING THE FABRIC BETWEEN THE POSTS AS EACH IS DRIVEN INTO THE SOIL. A MINIMUM OF 12 INCHES OF THE FILTER FABRIC SHOULD EXTEND INTO THE TRENCH. (IF IT IS NECESSARY TO JOIN THE ENDS OF TWO FENCES.

5. LAY THE FOUR INCHES OF FILTER FABRIC ON THE BOTTOM OF THE TRENCH AND EXTEND IT TOWARD THE

UP-SLOPE SIDE OF THE TRENCH. 6. BACKFILL THE TRENCH WITH SOIL MATERIAL AND COMPACT IT IN PLACE.

NOTE: IF THE SILT FENCE IS BEING CONSTRUCTED ON-SITE, ATTACH THE FILTER FABRIC TO THE SUPPORT POSTS (REFER TO TABLES 1 AND 2 FOR SPACING AND GEOTEXTILE SPECIFICATIONS) AND ATTACH WOODEN LATHE TO SECURE THE FABRIC TO THE POSTS. ALLOW FOR AT LEAST 12 INCHES OF FABRIC BELOW GROUND LEVEL. COMPLETE THE SILT FENCE INSTALLATION, FOLLOWING STEPS 1 THROUGH 6

 INSPECT WITHIN 24 HOURS OF A RAIN EVENT AND AT LEAST ONCE EVERY SEVEN CALENDAR DAYS.
 IF FENCE FABRIC TEARS, STARTS TO DECOMPOSE, OR IN ANY WAY BECOMES INEFFECTIVE, REPLACE THE AFFECTED PORTION IMMÉDIATELY. ALL REPAIRS SHOULD MEET SPECIFICATIONS AS OUTLINED WITHIN THIS

REMOVE DEPOSITED SEDIMENT WHEN IT IS CAUSING THE FILTER FABRIC TO BULGE OR WHEN IT REACHES ON—HALF THE HEIGHT OF THE FENCE AT ITS LOWEST POINT. WHEN CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED, REMOVE THE FENCE AND SEDIMENT DEPOSITS, GRADE THE SITE TO BLEND WITH THE SURROUNDING AREA, AND STABILIZE.

> NOTE: SILT FENCE <u>IS NOT</u> RECOMMENDED FOR USE AS A DIVERSION AND SHOULD NOT BE USED ACROSS A STREAM, CHANNEL, DITCH, SWALE, OR ANYWHERE THAT CONCENTRATED FLOW IS ANTICIPATED.

GRADING PROJECT 123 JOHN ST. NOBLESVILLE, IN

BLUE SKY EARLY


RELOCATION AND

ACTION UTILITY

STRUCTUREPOINT

7260 Shadeland Station | Indianapolis, Indiana 46256 TEL 317.547.5580 | FAX 317.543.0270

www.structurepoint.com



ISSUANCE INDEX
DATE:
07/24/2015
PROJECT PHASE:
CONSTRUCTION DOCUMENTS
•

REVISION SCHEDULE			
NO.	DESCRIPTION	DATE	
\triangle	ADDENDUM #1	08/04/15	


Project Number 2014.02717

EROSION CONTROL DETAILS




MAINTENANCE OF TRAFFIC NOTES

- CONTRACTOR IS RESPONSIBLE FOR MAINTAINING A SAFE MAINTANANCE OF TRAFFIC PLAN IN ACCORDANCE WITH LOCAL AND INDOT STANDARDS.
- 2. ALL TRAFFIC CONSTRUCTION SIGNAGE METHODS, MATERIALS AND CONSTRUCTION DETAILS SHALL CONFORM WITH LOCAL AND INDOT STANDARD SPECIFICATIONS AND THE INDIANA MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.
- 3. BARRICADES OR DRUMS SHALL BE PLACED ALONG THE OUTSIDE 2 FT. OF THE EXISTING PAVEMENT DURING CONSTRUCTION @ 20' O.C. DRUMS SHALL BE EQUIPPED WITH STEADY BURN LIGHTS.
- 4. MAINTAIN 11' MINIMUM LANE DURING CONSTRUCTION.
- 5. CONTRACTOR IS RESPONSIBLE FOR ALL TEMPORARY SIGNAGE FOR ON-STREET PARKING CLOSURES AND NOTIFICATIONS.



TRAFFIC SIGNS




= BLACK OR OTHER APPROVED COLOR

STANDARD DRUM BARRICADE DETAIL NOT TO SCALE


White paint in accordance with

Standard specifications.



DETAIL OF TRAFFIC SIGN STANDARD

NOT TO SCALE



COMMENCING ANY CONSTRUCTION. CONTACT

3. SEE ALL NOTES ON GENERAL NOTES SHEET 002.

ENGINEER IF VARIATION EXISTS.

CONTROL DEVICES, THIS INCLUDES PLACING ROAD

CONSTRUCTION AHEAD SIGNS, LANE MERGING SIGNS,

FLASHING ARROW SIGNS, CONSTRUCTION BARRELS,

TO ANY AND ALL CONSTRUCTION.

1-800-382-5544

CALL TOLL FREE

INDIANA UNDERGROUND

www.structurepoint.com

11500313 STATE OF

CERTIFIED BY


ADDENDUM #1

CLOSURE

~~~

08/04/15

2014.02717



7260 Shadeland Station | Indianapolis, Indiana 46256
TEL 317.547.5580 | FAX 317.543.0270

www.structurepoint.com

BLUE SKY EARLY
ACTION UTILITY
RELOCATION AND
GRADING PROJECT

123 JOHN ST. NOBLESVILLE, IN



| ISSUANCE INDEX         |
|------------------------|
| DATE:                  |
| 07/24/2015             |
| PROJECT PHASE:         |
| CONSTRUCTION DOCUMENTS |

| REVISION SCHEDULE |             |          |  |  |
|-------------------|-------------|----------|--|--|
| NO.               | DESCRIPTION | DATE     |  |  |
| $\triangle$       | ADDENDUM #1 | 08/04/15 |  |  |
|                   |             |          |  |  |
|                   |             |          |  |  |
|                   |             |          |  |  |
|                   |             |          |  |  |
|                   |             |          |  |  |
|                   |             |          |  |  |
|                   |             |          |  |  |
|                   |             |          |  |  |
|                   |             |          |  |  |
|                   |             |          |  |  |

Project Number 2014.02717

MAINTENANCE OF TRAFFIC / JOHN ST. CLOSURE

**C602** 

|                                                        |                |                                                  |                          |          |                                              |                                  |                                              |                            | PRE-QUAL             | STATUS              |         |                                                  |
|--------------------------------------------------------|----------------|--------------------------------------------------|--------------------------|----------|----------------------------------------------|----------------------------------|----------------------------------------------|----------------------------|----------------------|---------------------|---------|--------------------------------------------------|
| NAME                                                   | PO BOX         | ADDRESS                                          |                          | STATE    | ZIP TELEPHONE                                | LOCATION                         | AMOUNT TYPE                                  | MAX PROJECT                | STATUS               | CODE EMR1           | EMR2    | EMR3 TRIR                                        |
| 3D                                                     | P.O. Box 12588 | 3257 Lochness Dr.                                | 3 - 3                    | KY       | 40583 (606) 272-6618                         | 75,80,85                         | Multiple                                     |                            | Approved             | A                   |         |                                                  |
| 3D Company, Inc.                                       |                | ,                                                |                          | IN       | 47303 (765) 288-3326                         | 10,15,46, 48, 60                 | \$250,000 Pipeline                           | 500,000.00                 |                      | A 1188              | 12-1.11 | 13110                                            |
| A & K Construction, Inc.  ADB Companies. Inc           |                | 540 Morland Dr<br>21 Progress Parkway            | · · · <b>,</b> · · · · · | IN<br>MO | 47905 (765) 447-2262<br>63084 (314) 426-5200 | All                              | Pipeline Pipeline                            | 1,000,000.00               | Approved             |                     | 11-1.21 | 12-1.00                                          |
| Angelo Iafrate Construction Co.                        |                | ,                                                |                          | MI       | 48091 (586) 756-1070                         | All                              | \$1,000,000 Pipeline                         |                            | Approved             |                     | 11-1.21 | 12-1.03                                          |
| Arexco, Inc                                            |                | 1784 Park View Drive                             |                          | IN       | 47460 812-829-2306                           | 70                               | \$250,000 Multiple                           | 1,500,000.00               |                      | A 1292              | 1388    | 1489                                             |
| B & D Sewers, Inc.                                     | P.O. Box 515   | P.O. Box 515                                     | •                        | IN       | 46375 (219) 322-2300                         | 90                               | Pipeline                                     | 1,500,000.00               |                      | A 0978              | 1079    | 11.81                                            |
| B & S Plumbing and Heating, Inc.                       |                | 889 W. Johnson Dr                                |                          | IN       | 47802 (812) 234-1152                         | 70                               | \$1,000,000 Multiple                         | 1,000,000.00               | Approved             | A 0881              | 0982    | 1078                                             |
| B & T Drainage & Excavating                            |                | 21715 E. 1350th Rd                               | Marshall                 | IL       | 62441 (217) 826-6591                         | 58 70                            | \$850,000 Pipeline                           | 850,000.00                 |                      | A 1098              | 1194    | 1291                                             |
| B L Construction & Excavation                          | PO Box 119     | 5111 W. State Road 132                           | Pendleton                | IN       | 46064 (765)778-4120                          | 10,15,25,40,48,50,55,58,60,65    | #05 000 B; I                                 | 250,000.00                 | Approved             | a 1089              | 1192    | 1292                                             |
| Barrett's Excavating Bastin Logan Water Services, Inc. |                | 497 S Harmony Rd<br>237 W. Monroe St.            |                          | IN<br>IN | 47840 (812) 208-6256<br>46131 (317) 738-4577 | 70<br>All                        | \$85,000 Pipeline Multiple 2                 |                            | Approved Approved    | A 12-1.01           | 13-1.31 | 14-1.1                                           |
| Beaty Construction, Inc.                               |                | 5292 West 100 North                              |                          | IN       | 46110 (317) 835-2254                         | 10,25,47,48,50,55,58,60,65,85    | \$2,500,000 Pipeline                         | 2,500,000.00               |                      | A 12-1.01<br>A 1282 | 13-1.51 | 14-1.1                                           |
| Beer & Slabaugh, Inc.                                  |                |                                                  |                          | IN       | 46550 (574) 773-3413                         | 46                               | \$300,000 Multiple                           | 1,000,000.00               |                      | A 1186              | 1284    | 1376                                             |
| Blankenberger Brother, Inc.                            |                | 11700 Water Tank Rd                              |                          | IN       | 47612 (812) 845-2717                         | 80                               | Unlimited Multiple                           | 20,000,000.00              |                      | A 0693              | 0781    | 0873                                             |
| BMB Inc                                                |                | 3614 Citadel Circle                              | Newburgh                 | IN       | 47630 (812) 867-5433                         | 70 71 80                         | \$250,000 Pipeline                           | 250,000.00                 |                      | A 1094              | 1185    | 1284                                             |
| Bowen Engineering Corporation                          |                | 8802 North Meridian St.                          | Indianapolis             | IN       | 46260 (317) 842-2616                         | All                              | Multiple                                     |                            | Approved             | A 0667              | 0771    | 0862                                             |
| Bowen Engineering Corp                                 |                | 233 SE 3rd St                                    |                          | IN       | 47713 (812) 475-3880                         | 80,75                            | Multiple                                     | 0.00                       | Approved             | A                   |         |                                                  |
| Bowen Engineering Corporation                          |                | 1110 Arrowhead Ct, #B                            |                          | IN       | 46307 (219) 661-9770                         | All                              | Multiple                                     |                            | Approved             | A                   |         |                                                  |
| Boyd Construction Company, Inc. Brackney, Inc          | P.O. Box 221   | 450 S. Ohio St<br>10028 US #52                   |                          | IN<br>IN | 46342 (219) 942-3215<br>47012 (765) 647-6551 | 90<br>All                        | Pipeline<br>\$5,000,000 Pipeline             | 5,000,000.00               | Approved             | Δ                   | +       | <del>                                     </del> |
| Brown's Excavating & Drainage LLC                      | F.O. DOX ZZ I  | 12110 Fox Rd                                     |                          | IN       | 47345 (765) 489-4213                         | 25                               | \$5,000,000 Pipeline<br>\$100,000 Pipeline   | 100,000.00                 |                      | A                   | +       | <del>                                     </del> |
| Brusco, Inc.                                           | P.O. Box 238   |                                                  | Franklin                 | IN       | 46131 (317) 738-9236                         | 55                               | Pipeline                                     |                            | Approved             | A                   |         |                                                  |
| Bryan Stumler Excavating, Inc.                         |                | 5895 Stiller Rd                                  |                          | IN       | 47119 (812) 923-9772                         | 55,75,85                         | \$1,000,000 Pipeline                         | 1,000,000.00               | Approved             | A 06-1.12           | 07-1.03 | 0899                                             |
| C & E Excavating, Inc.                                 |                | 53767 CR 9                                       | Elkhart                  | IN       | 46514 (574) 262-4346                         | 10,30,45,46,90                   | \$1,000,000 Pipeline                         | 1,000,000.00               | Approved             | A                   |         |                                                  |
| Caldwell Tanks, Inc                                    | P.O. Box 35770 | 4000 Tower Rd                                    |                          | KY       | 40232 (502) 964-3361                         | All                              | \$3,500 Tank-Steel                           | 3,500,000.00               |                      | A 0760              | 0859    | 0959                                             |
| Carver Construction                                    |                | 1005 West Bethel                                 |                          | IN       | 47342 (765) 759-5265                         | 10,15,40                         | Pipeline                                     |                            | Approved             | Α                   |         | 12.24                                            |
| CAT Excavating                                         | P.O. Box 246   | 5424 E. 1050 S.                                  |                          | IN       | 46940 (765) 981-4877<br>46140 (317) 894-1990 | 45                               | Pipeline                                     | 0.00                       | Approved             | A 0887              | 0981    | 1084                                             |
| Central Engineering & Cstrtn Assc. CK Excavating, Inc. |                | 3862 N. Commercial Pky<br>3081 W. Winnerline Rd. |                          | IN<br>OH | 45320 (937) 472-3948                         | All except 90<br>25              | \$1,500,000 Pipeline<br>\$300,000 Pipeline   | 1,500,000.00<br>300,000.00 |                      | Α                   |         |                                                  |
| Clover Excavating & Trucking                           |                | 5916 Waubesa Way                                 |                          | IN       | 46901 (765) 453-2044                         | 10                               | Pipeline                                     | 300,000.00                 | Approved             | A                   |         |                                                  |
| Conex, Inc.                                            |                | G-4376 Beech Rd                                  |                          | MI       | 48532 (810) 230-1066                         | 46                               | \$500.000 Multiple                           | 500,000.00                 |                      | A                   |         |                                                  |
| Connor Excavating, Inc.                                |                | 920 N. 1075 E                                    | Crawfordsville           | IN       | 47933 (765) 794-4084                         | 50                               | Pipeline                                     | ,                          | Approved             | A                   |         |                                                  |
| Construction Management & Design, Inc.                 |                |                                                  | Plymouth                 | IN       | 46563 (574) 935-6666 ext 25                  | All                              | \$100,000 Pipeline                           | 100000                     | Approved             | A 09-1.1            | 10-0.9  | 11-0.9                                           |
| Construction Services Indiana (CSI)                    |                | 3 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1          | Warsaw                   | IN       | 46580 (574) 268-2972                         | 45 & 46                          | Pipeline                                     |                            | Approved             |                     |         |                                                  |
| Cornell Harbison Excavating, Inc                       |                |                                                  |                          | IN       | 47122 (812) 923-1282                         | 75                               | Pipeline                                     | 2 222 222                  | Approved             | A                   | 10.1.00 | 10.1                                             |
| Crider & Crider, Inc                                   |                | 1900 Liberty Drive                               |                          | IN       | 47403 (812) 336-4452<br>46567 (574) 834-2643 | All except 30,35,51,58, 90<br>46 | \$2,000,000 Pipeline<br>\$350,000 Pipeline   |                            | ripprovou            |                     | 12-1.06 | 13-1                                             |
| Cripe Excavating, Inc. Cristiani Excavating Co, Inc.   |                | 8837 N Syra-Web Rd.<br>1221 Old Hwy 31E          | ,                        | IN<br>IN | 47129 (812) 282-9908                         | 75,80                            | \$350,000 Pipeline Pipeline                  | 350,000.00                 | Approved<br>Approved | A 1283              | 13_1_01 | 1493 2.471                                       |
| Culy Construction & Excavating, Inc.                   | P.O. Box 29    |                                                  |                          | IN       | 47394 (765) 584-8509                         | 50,55,58,60,65,70                | \$600,000 Pipeline                           | 600,000.00                 | Approved             | A 1297              |         | 1481 1.191                                       |
| D & D Hunt, Inc.                                       | P.O. Box 66    |                                                  | Shelbyville              | IN       | 46176 (317)392-1599                          | 65                               | Pipeline                                     | 000,000.00                 | Approved             | A 12.07             | 10.01   | 11.01                                            |
| Dashiell Contracting                                   |                | P.O. Box 191                                     | Marshall                 | IL       | 62441 (217) 826-8194                         | 50,58,70                         | \$500,000 Multiple                           | 500,000.00                 |                      | A 1298              | 1396    | 1496                                             |
| Dave O'Mara Contractors, Inc.                          | PO Box 1139    | 1100 E. O & M Ave.                               | North Vernon             | IN       | 47265 (812) 346-4135                         | 25-85                            | Unlimited Pipeline                           | 20,000,000.00              |                      |                     |         | 1191 5.13                                        |
| Dave's Excavating, Inc.                                |                | 401 W. 33rd St.                                  |                          | IN       | 46953 (765) 674-8188                         | All but 75 & 90                  | \$1,000,000 Multiple                         |                            | Approved             |                     | 10-1.29 | 1185                                             |
| David Price Excavating                                 |                | 2261 Traction Rd                                 | Crawfordsville           |          | 47933 (765) 362-8895                         | 50                               | Pipeline                                     |                            | Approved             | A 1293              | 1389    | 10.0.07                                          |
| Davidson Excavating, Inc.                              |                |                                                  |                          | IN<br>IN | 46979 (765) 883-7876<br>46404 (219) 944-1810 | See pg 12<br>90                  | \$2,000,000 Pipeline Unlimited Paving        |                            | Approved             |                     | 11-0.85 | 12-0.87                                          |
| Day's Asphalt Paving, Inc. de Boer Egolf Corp.         |                | 855 Taft Street<br>5772 Melton Rd                | /                        | IN       | 46368 (219) 763-9703                         | 90                               | \$1,500,000 Pipeline                         |                            | Approved Approved    |                     | 0798    | 0885                                             |
| Deichman Excavating                                    |                | 2245 S. 150 E.                                   |                          | IN       | 46947 (574) 722-7677                         | 90                               | Multiple                                     |                            | Approved             |                     |         | 0893                                             |
| Deig Brothers, Inc.                                    |                | 2804 "A" St                                      |                          | IN       | 47712 (812) 423-4201                         | 80                               | \$10,000,000 Multiple                        | 10,000,000.00              |                      |                     | 0765    |                                                  |
| Delta III, Inc                                         |                | 6063 W. 1250 S.                                  |                          | IN       | 46340 (219) 797-4004                         | 90                               | Pipeline                                     | 0.00                       | Approved             | A                   |         |                                                  |
| Dennis Trucking Company, Inc.                          |                | 2900 N. 25th St                                  |                          | IN       | 47804 (812) 466-4271                         | 70,71                            | \$500,000 Multiple                           |                            | Approved             |                     | 0980    | 1096                                             |
| Dotlich Contractors, Inc.                              |                | 4090 N. 575 E.                                   |                          | IN       | 46112 (317) 858-0850                         | 55                               | Pipeline                                     |                            | Approved             |                     | 10 ==   | 11. 75                                           |
| Dyer Construction                                      |                |                                                  | ,                        | IN       | 46311 (219) 865-2961                         | 90                               | Pipeline                                     |                            | Approved             |                     | 1372    | 1473 3.265                                       |
| Eads & Son Bulldozing Eagle Valley, Inc                |                | 4141 N 400 E<br>3401 N. Raceway Rd.              |                          | IN<br>IN | 46941 (260) 774-3582<br>46234 (317) 291-8104 | 30,40,45,46,47<br>50-70          | \$300,000 Pipeline<br>\$1,000,000 Pipeline   |                            | Approved Approved    |                     | 0892    | 00-01                                            |
| Earth Resources aka D&R Exc.                           |                | 7210 S. State Road 267                           | <u> </u>                 | IN       | 46052 (317) 769-4966                         | 47,50,55,58,60                   | \$1,000,000 Pipeline<br>\$1,000.000 Multiple |                            | Approved             |                     | 0892    |                                                  |
| Eaton Excavating                                       |                |                                                  |                          | IN       | 46122 (317) 745-2414                         | 50,55,58,60,47                   | \$250,000 Multiple                           |                            | Approved             |                     | 1187    |                                                  |
| Elevation Excavation, Inc.                             |                |                                                  |                          | IN       | 46032 (317) 816-3149                         | 10,50,55,58,60,65                | \$200,000 Pipeline                           |                            | Approved             |                     | 10-1.04 |                                                  |
| Enterprise Excavating, LLC                             |                | 5340 Commerce Circle, Suite C                    | Indianapolis             | IN       | 46237 (317) 881-4554                         | All                              | \$1,000,000 Pipeline                         | 1,000,000.00               | Approved             | A                   |         |                                                  |
| Environmental Construction (ECI)                       |                | 13150 W. CR 300 N                                |                          | IN       | 47396 (765) 759-6145                         |                                  | Multiple                                     |                            | Approved             |                     |         | 14-2.02 8.107                                    |
| Everett J. Prescott, Inc.                              |                | 8309 W. Washington St                            |                          | IN       | 46231 (317) 908-6740                         | All                              | \$250,000 Hot taps, Line stops               |                            | Approved             |                     | 09-1.03 |                                                  |
| Excel Excavating                                       |                | 5710 Utica Sellersburg Rd.                       | •                        | IN       | 47172 (812) 246-0857                         | 75                               | \$500,000 Pipeline                           |                            | Approved             |                     | 40. 77  | 1482                                             |
| F & K Construction, Inc.                               | P.O. Box 4427  | 2055 W 150 S<br>3481 Concord Road                |                          | IN       | 46929 (574) 967-4543<br>47909 (765) 477-7431 | 10 45,47,50,55,60                | \$1,500,000 Pipeline<br>\$1,500,000 Multiple |                            | Approved             |                     |         | 14-1.04 6<br>1472 1.168                          |
| Fairfield Contractors, Inc. Fetters Construction, Inc. | P.O. BOX 4427  |                                                  |                          | IN<br>IN | 46706 (260) 927-0040                         | 47,50<br>45, 46                  | \$1,500,000 Multiple<br>\$1,500,000 Multiple |                            | Approved Approved    |                     |         | 1472   1.168<br>  09-1.08                        |
| Feutz Contractors, Inc.                                | P.O. Box 130   | 1120 N. Main St                                  | Paris                    | II       | 61944 (217) 465-8402                         | 70                               | \$1,500,000 Multiple<br>\$500,000 Pipeline   |                            | Approved             |                     | 1381    | 5.348                                            |
| Filcon Construction, LLC                               | 1 .O. DOX 100  | 915 Deatsville Rd                                |                          | KY       | 40013 (502) 349-9110                         | 75                               | \$1,000,000 Multiple                         |                            | Approved             |                     | _       |                                                  |
| Fishers Contracting, LLC                               |                | 6125 S East St, Suite B                          |                          | IN       | 46227 (317) 945-7928                         | 15, 55, 58, 60, 65, 70           | \$250,000 Pipeline                           |                            | Approved             |                     | 1       | <u> </u>                                         |
| Fleming Excavating, Inc.                               |                | 112 E 1000 N                                     |                          | IN       | 46733 (260) 724-2697                         | 45,46,48                         | \$1,500,000 Pipeline                         |                            | Approved             |                     |         |                                                  |
| Fox Contractors Corp.                                  |                |                                                  | _                        | IN       | 46809 (260) 747-7717                         | 10, 15, 45, 46, 47, 55, 65       | \$250,000 Pipeline                           |                            | Approved             |                     | 1382    |                                                  |
| Furmanite America                                      |                | 10 Eisenhower Ln N                               | Lombard                  | IL       | 60148 (630) 435-9500                         | All                              | \$3,000,000 Pipeline                         |                            | Approved             |                     | 0758    | 0850                                             |
| G & G Hauling & Exc., Inc.                             |                | 3567 W 100 N                                     | Warsaw                   | IN       | 46580 (574) 267-3570                         | 46                               | \$3,000,000 Multiple                         | 3,000,000.00               | Approved             | A                   |         |                                                  |

|                                                                              |                                 |                                                     |                              |          |                                              |                                     |                                                       | PRE-QUAL                                        | STATUS                 |                 |              |                                                  |
|------------------------------------------------------------------------------|---------------------------------|-----------------------------------------------------|------------------------------|----------|----------------------------------------------|-------------------------------------|-------------------------------------------------------|-------------------------------------------------|------------------------|-----------------|--------------|--------------------------------------------------|
| NAME                                                                         | PO BOX                          | ADDRESS                                             | CITY                         | STATE    |                                              | LOCATION                            | AMOUNT TYPE                                           | MAX PROJECT STATUS                              | CODE EMR1              | EMR2            | EMR3         | TRIR                                             |
| G.E. Marshall, Inc.                                                          | P.O. Box 242                    | 1351 Joliet RdPO Box 242                            | Valparaiso                   | IN       | 46384 (219) 462-3415                         | 90, 47                              | \$10,000,000 Pipeline                                 | 10,000,000.00 Approved                          | A 1276                 | 1381            | 1488         | 2.7                                              |
| Gatlin Plumbing & Heating, Inc. Geiger Developing, Inc.                      |                                 | 1111 East Main St<br>4110 Lower Huntington Rd.      | Griffith Fort Wayne          | IN<br>IN | 46319 (219) 942-6972<br>46809 (260) 969-0760 | 90<br>45, 46                        | \$5,000,000 Pipeline<br>\$1,300,000 Pipeline          | 5,000,000.00 Approved<br>1,300,000.00 Approved  | A 0791                 | 0887            | 0992         |                                                  |
| Good Excavating & Hauling, LLC                                               |                                 | 3660 North 500 West                                 | Warsaw                       | IN       | 46582 (574) 858-9524                         | 10,15,45,46,60                      | \$1,300,000 Pipeline<br>\$100,000 Multiple            | 100,000.00 Approved                             | A 07-1.0               | 08-1.0          | 09-1.0       | -                                                |
| Gough, Inc.                                                                  |                                 | 2200 E. 88th Dr                                     | Merrillville                 | IN       | 46410 (219) 756-2200                         | 90                                  | \$15,000,000 Pipeline                                 | 15,000,000.00 Approved                          |                        |                 | 1465         | 3.451                                            |
| Grade A Excavating                                                           |                                 | 5300 Hessler Rd.                                    | Muncie                       | IN       | 47304 (765) 282-2218                         | 15, 60                              | \$250,000 Pipeline                                    | 250,000.00 Approved                             | A                      |                 |              |                                                  |
| Gradex, Inc                                                                  | D.O. Pay 70                     | 12900 N Meridian St, Sutie 120                      | Carmel                       | IN       | 46032 (317) 573-3970                         | All                                 | \$300,000 Pipeline                                    | 300,000.00 Approved                             | A 11-1.05              |                 | 13-1.04      |                                                  |
| Graham's Trucking & Excavating Graves Plumbing/2016 will be Graves Construct | P.O. Box 70<br>ion P.O. Box 238 | 6399 West State Road 54                             | Crown Point Switz City       | IN<br>IN | 46307 (219) 374-5124<br>47465 (812) 659-3138 | 90<br>47. 85                        | \$50,000 Pipeline<br>\$500,000 Pipeline               | 50,000.00 Approved<br>500,000.00 Approved       | A 1088                 | 1187            | 1287         |                                                  |
| Craves Flambing/2010 will be Craves Constitute                               | 1 .O. BOX 200                   | COSS West State Road 54                             | OWILE OILY                   | 1111     | 47 400 (612) 663 6166                        | 10, 60, 47, 50, 55, 58, 65, 70, 71, | wood,ood i ipemie                                     | 000,000.00 / (pproved                           | 7.                     |                 |              |                                                  |
| Graves Plumbing                                                              | P.O. Box 238                    | 6399 West State Road 54                             | Switz City                   | in       | 47465 (812) 659-3138                         | 75, 80, 85                          | Plant                                                 | 2,000,000.00 Approved                           | A 1176                 | 1274            | 1371         |                                                  |
| Grimmer Construction, Inc.                                                   |                                 | 2619 Main St                                        | Highland                     | IN       | 46322 (219) 924-1623                         | 90                                  | \$8,000,000 Pipeline                                  | 8,000,000.00 Approved                           |                        | 13-1.060        |              |                                                  |
| H&G Underground Utilities, LLC Hanks Construction, Inc.                      |                                 | 1356 E. State Road 2<br>559 N. State Road 15        | LaPorte<br>Wabash            | IN<br>IN | 46350 (219) 362-1632<br>46992 (260) 563-7713 | All 45                              | \$500,000 Pipeline<br>\$200,000 Multiple              | 500,000.00 Approved<br>200,000.00 Approved      | A 1284                 | 13-1.05         | 14-1.4       | 11.22                                            |
| Hartman Walsh Corporation                                                    |                                 | 7144 N. Market                                      | St. Louis                    | MO       | 63133 (314) 863-1800                         | All                                 | \$15,000,000 Multiple                                 | 15,000,000.00 Approved                          | A 0687                 | 0777            | 0881         | <del>                                     </del> |
| Harvey Construction Co, Inc                                                  |                                 | 9125 E. 146th Street                                | Noblesville                  | IN       | 46060 (317) 773-7565                         | 10,15,47,55,60                      | \$500,000 Multiple                                    | 500,000.00 Approved                             |                        |                 | 09-289       |                                                  |
| Haskins Underground, Inc                                                     |                                 | 8111 9B Road                                        | Plymouth                     | IN       | 46563 (574) 935-3151                         | 46, 90                              | \$1,500,000 Multiple                                  | 1,500,000.00 Approved                           | A 1290                 | 1390            | 1490         |                                                  |
| Hasse Construction Company, Inc. HIS Constructors. Inc                       | P.O. Box 300                    | P.O. Box 300<br>5150 E 65th Street, Suite B         | Calumet City<br>Indianapolis | IL<br>IN | 60409 (219) 932-1611<br>46220 (317) 284-1195 | 90<br>55                            | Pipeline<br>\$250,000 Pipeline                        | Approved 250,000.00 Approved                    | A 1280                 | 1391            | 1498         |                                                  |
| Hitzfield Excavating                                                         |                                 | 5009 E. 700 N.                                      | Roanoke                      | IN       | 46783 (260) 672-8836                         | 45,46,47                            | \$250,000 Pipeline<br>\$100,000 Multiple              | 100,000.00 Approved                             |                        |                 | 1087         | ++                                               |
| Holton Construction                                                          |                                 | 8807 Gentlewind Way                                 | Louisville                   | IN       | 40291 (502) 817-8498                         | 75                                  | \$150,000 Pipeline                                    | 150,000.00 Approved                             | A 1198                 |                 | 1398         |                                                  |
| HRP Construction                                                             | P.O. Box 266                    | 5777 Cleveland Rd                                   | South Bend                   | IN       | 46628 (574) 271-7800                         | 10,45,46,47,90                      | \$1,500,000 Pipeline                                  | 1,500,000.00 Approved                           | A                      |                 |              |                                                  |
| HyGrade Excavating, Inc                                                      |                                 | 5062 W Base Rd                                      | Greensburg                   | IN       | 47240 (812) 593-4176                         | 55, 60, 65                          | \$250,000 Pipeline                                    | 250,000.00 Approved                             | A 1193                 |                 | 13-1.09      |                                                  |
| Illiana Remedial Action, Inc. Infrastructure Systems, Inc. (ISI)             | P.O. Box 148                    | 6550 Osborn Ave<br>260 W. Vincennes St.             | Hammond<br>Orleans           | IN<br>IN | 46320 (219) 844-4862<br>47452 (812) 865-3309 | 90<br>All                           | \$250,000 Site Work<br>\$15,000,000 Pipeline          | 250,000.00 Approved<br>15,000,000.00 Approved   | A 08-1.02<br>A 1284    | 0977<br>1379    | 1080         | 4.147                                            |
| Jerry Aigner Construction                                                    | F.O. BOX 140                    | 944 N. Baker Rd.                                    | Boonville                    | IN       | 47601 (812) 897-5815                         | 80                                  | \$700,000 Multiple                                    | 700,000.00 Approved                             | A 1204                 | 1373            |              | 4.147                                            |
| Joe Spiker Excavating, Inc.                                                  | P.O. Box 241                    | 1095 W Co Rd 125 S                                  | Greencastle                  | IN       | 46135 (765) 653-1512                         | 70                                  | \$100,000 Pipeline                                    | 100,000.00 Approved                             | A 0983                 | 1083            | 1183         |                                                  |
| Johnson Excavating Co., Inc.                                                 |                                 | 16 W. US Highway 6                                  | Valparaiso                   | IN       | 46383 (219) 462-8013                         | 90                                  | Pipeline                                              | Approved                                        | Α                      |                 |              |                                                  |
| Kelsey Construction, LLC                                                     |                                 | 4530 Merchant Rd<br>212 Cedar Grove Road            | Fort Wayne<br>Shepherdsivlle | IN<br>IN | 46818 (260) 497-9000<br>40165 (502) 955-1410 | All 75, 85                          | \$250,000 Pipeline<br>\$200,000 Multiple              | 250,000.00 Approved                             | A 0981<br>A 1280       | 1083<br>1383    | 1183<br>1498 |                                                  |
| Kettelhut Construction                                                       | P.O.Box 5000                    | 740 Sagamore Pkwy S                                 | Lafayette                    | IN       | 47905 (765) 447-2181                         | 47                                  | \$250,000 Multiple                                    | 500,000.00 Approved<br>250,000.00 Approved      | A 0778                 | 0887            | 0983         | +                                                |
| King's Trucking & Excavating, Inc.                                           |                                 | 9804 E. CR 800 N                                    | Seymour                      | IN       | 47274 (812) 523-8484                         | 55, 65, 75, 85                      | \$1.000.000 Multiple                                  | 1,000,000.00 Approved                           |                        |                 | 1475         |                                                  |
| Knott Drainage & Excavating, Inc.                                            |                                 | 6422 State Road 205                                 | Laotto                       | IN       | 46763 (260) 357-5424                         | 46                                  | \$150,000 Multiple                                    | 150,000.00 Approved                             | A 0795                 | 0880            | 0982         |                                                  |
| Kokosing                                                                     | D.O. D 00407                    | 6235 Westerville Road                               | Westerville                  | OH       | 43081 (614) 212-5698                         | 47                                  | #0.000 000 Bin alin a                                 | Approved                                        |                        | 1389            | 00.70        | 2.675                                            |
| Kreager Brothers Excavating, Inc. Lankford Excavating                        | P.O. Box 80187                  | P.O. Box 80187<br>3688 N. Creal                     | Fort Wayne Terre Haute       | IN<br>IN | 46898 (219) 482-4445<br>47804 (812) 877-1947 | 47<br>70                            | \$2,000,000 Pipeline Pipeline                         | 2,000,000.00 Approved Approved                  |                        | 0787<br>13-1.36 | 0873         | ++                                               |
| Larson-Danielson Costrcto Co., Inc.                                          |                                 | 302 Tyler St                                        | LaPorte                      | IN       | 46350 (219) 362-2127                         | 45, 90                              | \$500,000 Pipeline                                    | 500,000.00 Approved                             | A 12.11.0              | 10 1.00         |              |                                                  |
| Lawyer Excavation, Inc.                                                      |                                 | 7841 N US Highway 31                                | Seymour                      | IN       | 47274 812-522-6467                           | 55, 65, 75, 85                      | \$200,000 Multiple                                    | 300,000.00 Approved                             | A 1285                 | 1381            |              | 2.425                                            |
| Layne Christensen Company                                                    |                                 | 1301 East Main St                                   | Louisville                   | KY       | 40206 (502) 585-4169                         | All                                 | \$5,000,000 WTP and SOS                               | 5,000,000.00 Approved                           | A 1288                 |                 |              | 3.474                                            |
| Layne Heavy Civil LGS Plumbing, Inc.                                         |                                 | 4520 N SR 37<br>1112 E. Summit St                   | Orleans Crown Point          | IN<br>IN | 47452 (812) 865-3232<br>46307 (219) 663-2177 | See pg 19<br>90                     | \$20,000,000 Water Facilities<br>\$6,000,000 Pipeline | 20,000,000.00 Approved<br>6,000,000.00 Approved |                        | 1384<br>10-1.06 |              | 4.113                                            |
| Limestone Products, Inc.                                                     | P.O. Box 618                    | 1401 W. Votaw St                                    | Portland                     | IN       | 47371 (260) 726-2042                         | 90                                  | \$250,000 Multiple                                    | 250,000.00 Approved                             | A 03-1.01              | 10-1.00         | 11-1.0       |                                                  |
| Maddox Industrial Contractors                                                |                                 | 8731 Americana Blvd                                 | Indianapolis                 | IN       | 46268 (317) 870-2400                         | All                                 | \$2,000,000 Plant                                     | 2,000,000.00 Approved                           | A                      |                 |              |                                                  |
| Majority Builders, Inc                                                       |                                 | 62900 US 31 South                                   | South Bend                   | IN       | 46614 (574) 291-7472                         | 90                                  | \$100,000 Multiple                                    | 100,000.00 Approved                             | A 0681                 | 0785            | 0889         |                                                  |
| Maken Corporation Margaret, LLC                                              |                                 | 3922 Bell Rd<br>216 Southmoor Rd                    | Newburgh<br>Hammond          | IN<br>IN | 47630 812-853-5261<br>46324 (219) 803-4514   | 80<br>90                            | \$250,000 Multiple<br>\$500,000 Pipeline              | Approved 500,000.00 Approved                    | a 1187<br>A 07-1.0     |                 |              |                                                  |
| McAllister, Inc.                                                             | P.O. Box 810                    | 10501-8A W 133rd Ave                                | Cedar Lake                   | IN       | 46303 (219) 374-9498                         | 90                                  | \$250,000 Pipeline                                    | 250,000.00 Approved                             |                        | 1083            |              | <del>                                     </del> |
| McConnell Excavating                                                         |                                 | 15804 State Rte 58                                  | Oberlin                      | ОН       | 44074 (440) 774-4578                         | 10,15,25,47,48,55                   | \$6,000,000 Multiple                                  | 6,000,000.00 Approved                           | A                      |                 |              |                                                  |
| Merrel Bierman Excvating, Inc.                                               |                                 | 1030 Sames Rd                                       | Clarksville                  | IN       | 47129 (812) 923-9546                         | 50, 75, 85                          | \$250,000 Multiple                                    | 250,000.00 Approved                             | A 0599                 | 06-1.09         | 0783         |                                                  |
| Meyers Mechanical Corp.  Midwest Mole, Inc.                                  | P.O. Box 1950                   | 6814 W 350 N                                        | Richmond<br>Greenfield       | IN<br>IN | 47375 (765) 966-0541<br>46140 (317)545-1335  | 25<br>All                           | Industrial Tooling<br>\$5,000,000 Pipeline            | 0.00 Approved<br>5,000,000.00 Approved          | A 10.0.77              | 11-0.88         | 12 0 00      |                                                  |
| Midwest Paving LLC                                                           |                                 | 16105 River Road                                    | Noblesville                  | IN       | 46062 (317) 776-8925                         | All                                 | \$3,000,000 Fipeline<br>\$250,000                     | 250,000.00 Approved                             |                        | NA              | NA           | 1                                                |
| Mike Delucio & Son Contractor                                                |                                 | 3436 Chester Blvd.                                  | Richmond                     | IN       | 47374 (765) 962-8010                         | 25                                  | \$750,000 Multiple                                    | 750,000.00 Approved                             |                        | 0898            | 0988         |                                                  |
| Milestone Contractors, L.P.                                                  | P.O. Box 6246                   | 3301 South CR 460 East                              | Lafayette                    | IN       | 47905 (765) 772-7500                         | 25, 85                              | \$2,000,000 Pipeline                                  | 2,000,000.00 Approved                           | A 1264                 | 1369            | 1469         | 2.394                                            |
| Millenium Contractors, LLD Miller Pipeline                                   | P.O. Box 1303                   | 1631 W. Thompson Rd, #235<br>8850 Crawfordsville Rd | Indianapolis<br>Indianapolis | IN<br>IN | 46217 (317) 780-0109<br>46234 (317) 293-0278 | 55,60,65<br>All                     | Multiple<br>\$2,000,000 Multiple                      | Approved                                        | A 1292                 | 1399            | 1495         | 2.470                                            |
| Mohr Construction Company                                                    |                                 | 1240 S. Union St                                    | Kokomo                       | IN       | 46902 (765) 459-3111                         | 10,15,60,45                         | \$2,000,000 Multiple Pipeline                         | Approved Approved                               |                        | 0780            |              | 2.479                                            |
| Neal Excavating                                                              |                                 | R.R. 2, Box 248                                     | Crawfordsville               | IN       | 47933 (317) 866-1172                         | 15,50                               | Pipeline                                              | Approved                                        | A   00 .50             | 07 .00          | 00 .70       |                                                  |
| Noland & Sons Excavating, Inc.                                               |                                 | 2515 East 00 North                                  | Kokomo                       | IN       | 46901 (765) 452-3532                         | 10                                  | Pipeline                                              | 500,000.00 Approved                             |                        | 1087            |              |                                                  |
| NY - KO Excavating                                                           |                                 | 5182 Chicago Dr                                     | Hudsonville                  | MI       | 49426 (616) 669-3698                         | 90, 50                              | \$100,000 Multiple                                    | 100,000.00 Approved                             |                        |                 | 0899         | 1                                                |
| Oles Engineering O'neal Excavating & Construction                            |                                 | 9500 N. 800 E.<br>14714 Lima Rd                     | Brownsburg Fort Wayne        | IN<br>IN | 46112 (317) 769-5946<br>46818 (260) 338-1609 | All but 90,70,75<br>46              | \$1,000,000 Pipeline<br>\$250,000 Pipeline            | 1,000,000.00 Approved<br>250,000.00 Approved    |                        | 0998<br>1087    | 1098         | -                                                |
| Ortman Drilling, Inc.                                                        |                                 | 241 N. County Rd. 300W                              | Kokomo                       | IN       | 46901 (765) 459-4125                         | All                                 | Well                                                  | 3,000,000.00 Approved                           | A 0967<br>A 07-1.10    |                 |              |                                                  |
| Pace Contracting, LLC                                                        |                                 | 200 Willinger Ln                                    | Jeffersonville               | IN       | 47130 (812) 283-5784                         | 50, 75, 85                          | \$950,000 Pipeline                                    | 950,000.00 Approved                             | A 07-1.11              | 08-1.05         | 0983         |                                                  |
| Pajay, Inc.                                                                  |                                 | 10601 Maudlin Rd                                    | New Buffalo                  | MI       | 49117 (616) 292-4462                         | Northwest                           | \$250,000 Pipeline                                    | 250,000.00 Approved                             | A 09-0.92              |                 |              |                                                  |
| Peerless-Midwest, Inc                                                        |                                 | 17707 Sun Park Dr.<br>7050 East Landersdale Rd      | Westfield                    | IN<br>IN | 46074 (317) 896-2987                         | All 50,58                           | Multiple                                              | 750,000.00 Approved                             | A 1295<br>A 06-1.02    |                 |              | 2.348                                            |
| Perry Excavating Peyronnin Cstrtn Company, Inc                               | P.O. Box 3317                   | 1901 N. Kentucky Ave                                | Camby<br>Evansville          | IN       | 46113 (317) 507-0715<br>47732 (812) 423-6241 | 80                                  | Pipeline Multiple                                     | Approved Approved                               | A 06-1.02<br>A 06-1.12 |                 |              | +                                                |
| Phend & Brown, Inc.                                                          | P.O. Box 150                    |                                                     | Milford                      | IN       | 46542 (574) 658-4166                         | 45, 46                              | Co. \$200,000/Dev \$500,000 Pipeline                  | 500,000.00 Approved                             |                        |                 | 1097         |                                                  |
| Plant Brothers Exc & Const Co, LLC                                           |                                 | 10650 Atherton St                                   | Rosedale                     | IN       | 47874 (812) 466-6975                         | 47, 50, 55, 58, 60, 65, 71          | Co. \$250,000/Dev \$1,000,000 Concrete                | 1,000,000.00 Approved                           | A 1283                 | 1378            | 1496         | 1.607                                            |
| Poindexter Excavating, Inc.                                                  | P.O. Box 36399                  | 10443 E. 56th St                                    | Indianapolis                 | IN       | 46236 (317) 823-6837                         | All but 75,90                       | \$1,000,000 Pipeline                                  | 1,000,000.00 Approved                           | A 07-1.13              |                 | 0982         |                                                  |
| R & W Contracting R.V. Sutton, Inc.                                          |                                 | 3131 Klondike Rd<br>175 West 1050 North             | West Lafayette Chesterton    | IN IN    | 47906 (765) 463-1174<br>46304 (219) 926-8825 | 10, 47, 50<br>90                    | \$250,000 Multiple Pipeline                           | 250,000.00 Approved<br>2,000,000.00 Approved    | A 0780<br>A 0678       |                 |              | +                                                |
| ra.v. Outton, mo.                                                            |                                 | TITO VVGSt TOJO INOITII                             | OHESIGHUH                    | 11.4     | TUJUH (219) 920-0020                         | ] 30                                | I ILIBEIIIE                                           | 2,000,000.00 Approved                           | ,,  0070               | 017.10          | 0014         |                                                  |

|                                           |               |                                     |                |       |       |                  |                               |             |                     |              | PRE-QUAL |           |         |         |       |
|-------------------------------------------|---------------|-------------------------------------|----------------|-------|-------|------------------|-------------------------------|-------------|---------------------|--------------|----------|-----------|---------|---------|-------|
| NAME                                      | PO BOX        | ADDRESS                             | CITY           | STATE | ZIP   | TELEPHONE        | LOCATION                      | AMOUNT      | TYPE                | MAX PROJECT  | STATUS   | CODE EMR1 | EMR2    | EMR3    | TRIR  |
| RCM Excavating, LLC                       |               | 7779 W. 850 North                   | Gaston         | IN    | 47342 | (765) 358-4782   | 10, 65                        | \$500,000   | Trucking            | 500,000.00   | Approved | A 08-1.0  | 0993    | 1091    |       |
| Reichelt Plumbing, Inc.                   | P.O. Box 177  | 451 Winston Court                   | Schererville   | IN    | 46375 | (219) 322-4906   | 10,45,46,47                   |             | Pipeline            | 0.00         | Approved | А         |         |         |       |
|                                           |               |                                     |                |       |       |                  |                               |             |                     |              |          |           |         |         |       |
|                                           |               |                                     |                |       |       |                  |                               |             |                     |              |          |           |         |         |       |
| Republic Companies, Inc Look in Comments  |               | 3101 N. Green River Rd, St 610      | Evansville     | IN    |       | (812) 457-7404   | 55,58,60,70,75,80,85          |             | Pipeline            | 0.00         | Approved | A         |         |         |       |
| Rex Construction Company, Inc.            |               | 700 Schiller Ave                    | Schererville   | IN    |       | (219) 322-8090   | 90                            |             | Pipeline            |              | Approved | A 1290    | 1392    | 1488    | 1.666 |
| Reynolds Service Tech., Inc.              | P.O. Box 2094 | P.O. Box 2094                       | Richmond       | IN    | 47375 |                  | 25                            | \$250,000   |                     | 250,000.00   | Approved | A         |         |         |       |
| Rhodes Construction Corporation           | P.O. Box 777  | P.O. Box 777                        | Crawfordsville | IN    |       | (317) 362-2986   | 50                            |             | Pipeline            |              | Approved | A         |         |         |       |
| Rick Jenkins Construction, Inc.           |               | 4301 South Sixth St                 | Terre Haute    | IN    | 47802 | (812) 299-4128   | 70                            | \$250,000   | Pipeline            | 250,000.00   | Approved | A         |         |         |       |
| Robinet Contracting, Inc.                 | P.O. Box 108  | P.O. Box 108                        | Cortland       | IN    |       | 8 (812) 522-2448 | 85                            |             | Pipeline            |              | Approved | A         |         |         |       |
| Robinson Trenching Co.                    |               | 9915 Southeastern Ave.              | Indianapolis   | IN    |       | (317) 862-3929   | 47                            |             | Pipeline            |              | Approved | A         |         |         |       |
| Rose City Construction, LLC               |               | 1304 Rose City Blvd.                | Richmond       | IN    |       | (765) 939-7673   | 25,48                         |             | Pipeline            |              | Approved | A         |         |         |       |
| Rudolf Excavating                         |               | 5410 N CR 900 E                     | Brownsburg     | IN    |       | (317) 858-9530   | All                           | \$1,000,000 |                     | 1,000,000.00 | Approved | A 1293    |         | 1485    |       |
| Sedam Contracting Corporation             |               | 226 West La Grange Rd               | Madison        | IN    | 47250 | (812) 866-5606   | 75                            |             | Pipeline            |              | Approved | A 06-1.09 |         | 08-1.02 |       |
| Shambaugh & Son, L.P.                     |               | 7614 Opportunity Dr                 | Fort Wayne     | IN    | 46801 | (260) 487-7777   | All                           | \$5,000,000 | Pipeline            | 5,000,000.00 | Approved | A 1258    | 1357    | 14586   | 1.687 |
| Shook Construction                        |               | 7330 E. 90th St.                    | Indianapolis   | IN    | 46256 | (317) 849-6066   | All                           | \$5,000,000 | Multiple            | 5,000,000.00 | Approved | A 1275    | 1383    | 1481    | 2.3   |
| Simmons Company, LLC                      | P.O. Box 330  | 1156 E 800 N                        | Pittsboro      | IN    |       | 7 (317) 892-5770 | 10,15,45,46,47,50,55          | \$300,000   | Multiple            | 300,000.00   | Approved | Α         |         |         |       |
| Site Restoration Services, Inc.           |               | 5225 E. 145th Ave                   | Crown Point    | IN    | 46307 | 7 (219) 743-8180 | 90                            | Unlimited   | Multipld            | 1,000,000.00 | Approved | A 0893    | 0994    | 1000    |       |
| Snow-n-Son, Inc.                          |               | 9543 Wicker Ave.                    | St. John       | IN    | 46373 | (219) 365-4844   | 90                            |             | Pipeline            |              | Approved | A         |         |         |       |
| South Central Contracting, LLC            | P.O. Box 1854 |                                     | Martinsville   | IN    | 46151 | (317) 339-9995   | 50, 55, 58, 60, 65            | \$200,000   | Pipeline            | \$200,000    | Approved | A         |         | 11-1.0  |       |
| Southern Indiana Excavating Corp.         | P.O. Box 257  | P.O. Box 257                        | Sellersburg    | IN    | 47172 | (812) 246-2329   | 75                            |             | Pipeline            |              | Approved | Α         |         |         |       |
| Spectra Tech, LLC                         |               | 16100 Allisonville Rd               | Noblesville    | IN    | 46060 | (317) 770-7506   | All                           | \$1,000,000 | Multiple            | 1,000,000.00 | Approved | A 12-1.05 | 1397    |         |       |
| Star Excavating                           | P.O. Box 67   | 7832 N. 900 W.                      | Bippus         | IN    | 46713 | (260) 344-1311   | 10,15,45,46,47,60             | \$1,000,000 | Multiple            | 1,000,000.00 | Approved | A 0784    | 0889    | 0978    |       |
| Stradtner Excavating, Inc.                | P.O. Box 601  | 715 W Sycamore St                   | Boonville      | IN    | 47601 | (812) 897-4025   | 80                            |             | Pipeline            |              | Approved | A         |         |         |       |
| Sub-Surface of Indiana, Inc               |               | 7225 West 700 South                 | Morgantown     | IN    | 46160 | 812-597-4195     | 55, 58, 60, 65, 85            | \$250,000   | Multiple            | 2000000      | Approved | A 0880    | 0979    | 1080    |       |
| Superior Excavating Soils & Services, LLC |               | 2816 E. Old State Rd 30             | Warsaw         | IN    | 46582 | (574) 372-3478   | 10,45,46,48                   | \$100,000   | Pipeline            | 100,000.00   | Approved | A 0687    | 07-1.38 | 08-1.5  |       |
| Swinney Bros. Excavating, Inc.            |               | 998 S. SR 67                        | Mooresville    | IN    | 46158 | 3 (317) 831-2081 | 55                            |             | Pipeline            |              | Approved | A         |         |         |       |
| Team Contracting, LLC                     |               | 14912 Railroad St                   | Memphis        | IN    |       | 8 (812) 294-3901 | 75, 85                        | \$2,000,000 | Multiple            | 2,000,000.00 | Approved | A 06-1.07 | 07-1.07 | 0892    |       |
| Temple & Temple Excavating & Paving, Inc. |               | 1364 S. State Rd 60                 | Salem          | IN    | 47167 | (812) 883-6644   | 75                            |             | Pipeline            |              | Approved | A         |         |         |       |
| The Snider Group                          | P.O. Box 281  | 10890 Andrade Dr                    | Zionsville     | IN    | 46077 | (317_ 873-5265   | 55, 60                        | \$500,000   | Pipeline            | 500,000.00   | Approved | A 0899    | 09-1.1  | 1088    |       |
|                                           |               |                                     |                |       |       |                  |                               |             |                     |              |          |           |         |         |       |
| Thieneman Construction                    |               | 17241 Foundation Parkway, Suite 100 | Westfield      | IN    |       | (317) 867-3462   |                               |             |                     |              | Approved | Α         |         |         | 7.84  |
| Tom's Construction, Inc.                  |               | 821 Cooper Ave.                     | St. Henry      | OH    |       | (419) 678-2457   | 15,25,48                      | \$325,000   |                     | 325,000.00   |          | Α         |         |         |       |
| TPI Utility Construction                  |               | 478 N C R 1100 East                 | Zionsville     | IN    |       | (317) 769-4777   | All but 90 & 75               | \$500,000   |                     |              | Approved | A 06-1.01 |         | 0884    |       |
| Tri-State Fire Protection, Inc.           | P.O. Box 70   | 10577 Oak Grove Rd                  | Newburgh       | IN    |       | (812) 853-9229   | 25,30,45,55,58,70,71,75,80,85 |             | Hot taps, Fire line |              | Approved | A 09-0.79 |         | 11-0.98 |       |
| TSI Paving                                | P.O. Box 1540 | 1638 E Market St                    | New Albany     | IN    |       | (812) 948-6691   | 75, 85                        | \$250,000   |                     | 250,000.00   | Approved | A 1082    | 1183    | 1289    |       |
| TSW Utility Solutions                     |               | 1970 Midwest Blvd                   | Indianapolis   | IN    |       | (317) 557-5033   | All                           | \$1,000,000 |                     | 1,000,000.00 |          | A         | 12-1.0  | 13-0.92 |       |
| United Infrastructure, LLC                | P.O. Box 611  | 4160 E. 196th St                    | Noblesville    | IN    |       | (317) 867-2048   | 10, 65                        | \$200,000   |                     | 200,000.00   | Approved | A 06-     | 0792    | 0888    |       |
| V & H Excavating                          |               | 402 Norbeh Dr                       | Hebron         | IN    |       | (219) 996-4040   | 90                            |             | Pipeline            |              | Approved | A         |         |         |       |
| Valenti-Held, Inc                         |               | 4937 Fieldstone Dr                  | Whitestown     | IN    | 46075 | (317) 7696922    | All but 90 & 75               | \$250,000   | Multiple            | 250,000.00   | Approved | A 0875    | 0968    | 1072    |       |