

DLZ INDIANA, LLC
138 North Delaware Street
Indianapolis, Indiana 46204

March 10, 2022

ADDENDUM NO. 1


RE: **City of Noblesville
Logan Street Bridge Enhancement**

TO: All Bidders and others to whom Plans and Specifications for the above referenced Project have been issued.

The items included in this Addendum are to become a part of the original Drawings and Project Manual as if included herein. Only these items are to be altered. The remainder of the original Drawings and Project Manual remain valid in their entirety.

CERTIFIED BY:




Jonathan Mooney, PLA
Registered Landscape Architect
State of Indiana No. LA20900152

PROJECT MANUAL

No Items.

DRAWINGS

<u>Drawing No.</u>	<u>Detail/Item</u>	<u>Action</u>
S1.0 (18 of 20)	11	REVISE the 3'-0" spacing of the adhesive anchors used to fasten the aluminum chase to the concrete wall to read 10'-0" o.c.
S1.0 (18 of 20)	Note 7	ADD a new note to read "7. ½" adhesive anchors shall be able to resist an ultimate tension force of 600 lbs and an ultimate shear force of 1200 lbs concurrently. 3/8" adhesive anchors shall be able to resist an ultimate tension force of 100 lbs and an ultimate shear force of 350 lbs concurrently."

ATTACHMENTS:

Drawing S1.0

END OF ADDENDUM No. 1

